


80% FED, 10% STATE, 10% OP, *** 80% FED, 13% STATE, 7% PP
 OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE
 *=SPECIALTY ITEMS

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 135TH	TRAFFIC SIGNALS SOUTHMOOR	TRAFFIC SIGNALS 131ST	TRAFFIC SIGNALS CREEK	TRAFFIC SIGNALS 131ST/HIGH	INTERCONNECT	NEW SIDEWALK/MULTI-USE	ORLAND PARK 100%	NEW SIDEWALK/MULTI-USE	PALOS PARK 100%	WATER MAIN/SAN SEWER	SPECIAL BRIDGE/RET WALL
				80% FED 20% STA	100% OP	80% FED 20% STA	100% OP	80% FED 20% STA	***	80% FED 20% STA	80% FED 20% STA	80% FED 20% OP	100% OP	80% FED 20% PP	100% PP	100% OP	80% FED 20% STA
				0003	0021	0021	0021	0021	0021	0021	0021	0028	0021	0028	0021	0043	0040
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500													
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	4		4												
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1												
* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2			1	1										
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2					1	1								
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	10989			1049	946	900	745	283	7066						
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	135			13	33	58	31								
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	349			141	64	115	29								
* 81028230	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA.	FOOT	9						9								
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	6065		2543	428	548	785	776	75			910				
* 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	9081		1070								8011				
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	624		624												
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	50		50												
* 81200260	CONDUIT EMBEDDED IN STRUCTURE, 3 1/2" DIA., PVC	FOOT	1020		1020												



FILE NAME = D:\6062-SHT-500.dgn
 USER NAME = Anthony.Pluta
 DESIGNED -
 DRAWN -
 CHECKED -
 PLOT DATE = 3/19/2013

REVISIONS
 REVISED -
 REVISED -
 REVISED -
 REVISED -

DATE = 03/13/13

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET 18 OF 26 SHEETS STA. TO STA.

F.A.P. RTE. 330
 SECTION 103R-5
 COUNTY COOK
 TOTAL SHEETS 778
 SHEET NO. 22
 CONTRACT NO. 60M62

ILLINOIS FED. AID PROJECT