● 131ST/HIGH SCHOOL ■ MULTI-USE PATH

(1) ORLAND FIRE PROTECTION DISTRICT (2) PALOS FIRE PROTECTION DISTRICT
~~••• 80% FED, 10% STATE, 10% OP;~~ ••• 80% FED, 13% STATE, 7% PP
OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE
•=SPECIALTY ITEMS

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: ROADWAY	LIGHTING	TRAFFIC SIGNALS 135TH	TRAFFIC SIGNALS SOUTHMOOR	TRAFFIC SIGNALS 131ST	TRAFFIC SIGNALS CREEK	TRAFFIC SIGNALS ~~131ST/HIGH~~	INTERCONNECT	NEW SIDEWALK/ ~~MULTI-USE~~	ORLAND PARK 100%	NEW SIDEWALK/ ~~MULTI-USE~~	PALOS PARK 100%	WATER MAIN/SAN SEWER	SPECIAL BRIDGE/RET WALL
					80% FED	100% OP	80% FED	100% OP	80% FED	•••	80% FED	80% FED	80% FED	100% OP	80% FED	100% PP	100% OP	80% FED
					20% STA		20% STA		20% STA		20% STA	20% STA	20% OP		20% PP			20% STA
					0003	0021	0021	0021	0021	0021	0021	0021	0028	0021	0028	0021	0043	0040
*	82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8		8												
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	540		540												
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	15		15												
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	53		53												
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	43		43												
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	44		44												
*	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1		1												
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	5			1	1	1	1	1							
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	9777								9777						
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	5632			703	1493	1748	1164	524							
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	9181			724	1549	1804	1206	545			724 (1)		2629 (2)		
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	15505			3021	3497	5306	2858	823							
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3426			535	878	346	821	846							
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	11665			2241	1822	4810	1981	811							

URS
100 S. WACKER DR.
SUITE 500
CHICAGO IL 60606
TEL (312)-939-1000
FAX (312)-939-4198

FILE NAME : D160M62-SHT-SOO.dgn	USER NAME : Anthony.Plutz	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE : 100.0000 ' / in.	CHECKED -	REVISED -
SHT.PLAN	PLOT DATE : 3/19/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 20 OF 26 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-5	COOK	778	24

CONTRACT NO. 60M62

ILLINOIS FED. AID PROJECT