

EARTHWORK SCHEDULE - 60M62 NORTH

	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	UNSUITABLE EXCAVATION CU YD	SUITABLE EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) FURNISHED EXCAVATION CU YD
US 45 (LAGRANGE ROAD) STATION 286+00 TO STATION 384+00					
TEMPORARY	2,390.18	1,792.63	2,060.47	1,776.01	16.62
STAGE 1	17,698.16	13,273.62	12,089.20	27,290.84	-14,017.22
STAGE 2	573.40	430.05	12.96	1,000.37	-570.32
STAGE 3	7,125.92	5,344.44	3,295.52	16,509.09	-11,164.65
STAGE 4	2,046.56	1,534.92	143.09	5,767.19	-4,232.27
TOTAL:	29,834.23	22,375.67	17,601.24	52,343.51	-29,967.84
131ST STREET					
TEMPORARY	64.7	48.5	0.0	5.7	42.9
STAGE A	3,612.3	2,709.2	683.3	87.4	2,621.8
STAGE B	1,851.3	1,388.5	360.4	279.2	1,109.3
STAGE C	293.4	220.1	24.2	70.7	149.4
SUBTOTAL:	5,821.7	4,366.3	1,067.9	442.9	3,923.4
135TH STREET					
TEMPORARY	49.0	36.8	153.0	342.9	-306.1
STAGE A	634.3	475.7	276.1	213.4	262.3
STAGE B	841.2	630.9	312.3	555.0	75.9
STAGE C	426.4	319.8	192.3	121.8	198.0
SUBTOTAL:	1,950.9	1,463.2	933.8	1,233.2	230.1
CREEK ROAD					
STAGE A	236.6	177.4	131.5	52.4	125.0
TOTAL:	37,843	28,383	19,734	54,072	-25,689

FILE NAME = D160M62-SHT-SCHEDULE01.dgn	USER NAME = Anthony.Plutz	DESIGNED - MJT	REVISED -
SHT.PLAN	PLOT SCALE = 100.0000' / in.	DRAWN - MJT	REVISED -
	PLOT DATE = 3/14/2013	CHECKED - ---	REVISED -
		DATE - 03/13/13	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-5	COOK	778	38
<b>SC-01</b>			CONTRACT NO. 60M62	
ILLINOIS FED. AID PROJECT				