SEE DRAWING PP-08
MATCH LINE STA. 332+00.00

MATCH LINE STA. 338+00.00
SEE DRAWING PP-10

KRIS TRAIL

332+07.70
86.05' LT

332+07.78
70.89' LT

90+89.51
PI (PATH)

91+31.71
PI (PATH)

RETAINING WALL NO. 5
SEE STRUCTURAL PLANS

92+06.81
PI (PATH)

334+43.20
87.00' LT

334+40.92
68.02' LT

334+52.33
CHURCH ENTR

20.4'

334+63.76
87.00' LT

334+62.20
73.98' LT

RETAINING WALL NO. 6
SEE STRUCTURAL PLANS

MULTI-USE PATH (10' WIDE)
SEE TYPICAL SECTION FOR DETAILS

COMB CONC CURB & GUTTER
TYPE B-6.24 (TYPICAL)

95+07.23
PI (PATH)

95+97.38
PI (PATH)

96+47.38
PI (PATH)

COMB CONC CURB & GUTTER
TYPE B-6.12 (TYPICAL)

25' R

COMB CONC CURB & GUTTER
TYPE B-6.12 (TYPICAL)

25' R

DC

332+32.94
45.00' LT

334+16.10
45.00' LT

DC

334+87.02
45.00' LT

PORTLAND CEMENT CONCRETE
PAVEMENT, 10" (JOINTED)

LANDSCAPE MEDIAN
SEE LANDSCAPING PLANS

34.0'

333+71.00
11.00' LT

CURVE
US45PCL-3

332+55.31
PT

11.0'

℄ US 45 (LAGRANGE RD)

US 45 (LAGRANGE RD)

COMB CONC CURB & GUTTER
TYPE B-6.18 (MODIFIED)

17.0'

34.0'

PORTLAND CEMENT CONCRETE
PAVEMENT, 10" (JOINTED)

333+75.96
67.28' RT

STRUCTURE NO. 016-Z007
SEE STRUCTURAL PLANS

PORTLAND CEMENT CONCRETE
SIDEWALK 5 INCH (6' WIDE)
ALONG RETAINING WALL

COMB CONC CURB & GUTTER
TYPE B-6.24 (TYPICAL)

335+97.47
67.28' RT

336+47.00
60.58' RT

HMA SURFACE COURSE, MIX D,
N50 (3 INCH) AGGREGATE BASE
COURSE TYPE B, 2" (7' WIDE)

LEGEND
= DETECTABLE WARNINGS
SEE STD 424001 TO 424031
= PAVEMENT WIDENING

NOTE:
1. FOR CURVE DATA SEE ALIGNMENT, TIES AND BENCHMARKS DRAWING AT-01 TO AT-05
2. FOR ROW CALL-OUTS SEE PLAT OF HIGHWAY SHEETS
3. FOR DRIVEWAY PAVEMENT DETAILS SEE DISTRICT 1 STANDARDS BD-01 AND BD-02.
4. FOR CURB RAMPS FOR SIDEWALKS REFER TO STANDARDS 424001 TO 424031 AND/OR AS DIRECTED BY THE ENGINEER.

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
GRADE CHECKED
BM. NOTED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
BY
DATE

720
715
710
705
700
695

VPI +33.42
EL. 708.28

+1.52%

PROPOSED PGL
SEE TYPICAL SECTIONS US 45

EXISTING GROUND LINE
℄ US 45

	706.11	EX. EL.	706.55	706.96	707.51	708.26	709.04	709.85	710.82	711.68	712.69	713.65	714.59	715.45
	707.80	PR. EL.	708.53	709.29	710.05	710.81	711.57	712.32	713.08	713.84	714.60	715.36	716.12	716.88

332+00 332+50 333+00 333+50 334+00 334+50 335+00 335+50 336+00 336+50 337+00 337+50 338+00

URS
100 S. WACKER DR.
SUITE 1600
CHICAGO, IL 60606
TEL (312)939-1000
FAX (312)939-4198

FILE NAME =	USER NAME = Anthony.Plutz	DESIGNED - JTF	REVISED -
D160M62-SHT-PLNPRF09.dgn		DRAWN - JTF	REVISED -
	PLOT SCALE = 40.000000 ' / in.	CHECKED - MJT	REVISED -
SHT_PLNPROF URBAN	PLOT DATE = 3/13/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED PLAN AND PROFILE – US 45 (LAGRANGE ROAD)

SCALE: 1"=20' | SHEET 9 OF 17 SHEETS | STA. 332+00.00 TO STA. 338+00.00

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-5	COOK	778	63
	PP-09	CONTRACT NO. 60M62		
		ILLINOIS FED. AID PROJECT		