RESTORATION OF WORK AREA

RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

NOTES FOR TEMPORARY TRAFFIC SIGNALS

- ALL CONTROL EQUIPMENT INCLUDING EMERGENCY PRE-EMPTION AND COMMUNICATION DEVICES FOR THE TEMPORARY TRAFFIC SIGNAL (S) (1)SHALL BE FURNISHED BY THE CONTRACTOR.
- 2 ONLY CONTROLLERS SUPPLIED BY ONE OF THE DISTRICT APPROVED CLOSED LOOP EQUIPMENT MANUFACTURERS WILL BE APPROVED FOR USE AT TEMPORARY SIGNAL LOCATIONS. ALL CONTROLLERS USED FOR TEMPORARY TRAFFIC SIGNALS SHALL BE FULLY ACTUATED NEMA MICROPROCESSOR BASED WITH RS232 DATA ENTRY PORTS COMPATIBLE WITH EXISTING MONITORING SOFTWARE APPROVED BY IDOT DISTRICT 1, INSTALLED IN A NEMA TSI OR TS2 CABINET. ONLY ONE BRAND OF CONTROLLER WILL BE ACCEPTED FOR ANY ONE CONTRACT.
- 3 ALL TRAFFIC SIGNAL SECTIONS SHALL BE 12" (300mm). HEADS SHALL BE PLACED AS INDICATED ON THE TEMPORARY TRAFFIC SIGNAL PLAN OR AS DIRECTED BY THE ENGINEER, THE CONTRACTOR SHALL FURNISH ENOUGH CABLE SLACK TO RELOCATE HEADS TO ANY POSITION ON THE SPAN WIRE OR AT LOCATIONS ILLUSTRATED ON THE PLANS FOR CONSTRUCTION STAGING. THE TEMPORARY TRAFFIC SIGNAL SHALL REMAIN IN OPERATION DURING ALL SIGNAL HEAD RELOCATIONS. EACH TEMPORARY TRAFFIC SIGNAL HEAD SHALL HAVE ITS OWN CABLE FROM THE CONTROLLER CABINET TO THE SIGNAL HEAD. ALL SIGNAL HEADS SHALL BE L.E.D.
- ALL EXISTING STREET NAME AND INTERSECTION REGULATORY SIGNS SHALL (4)BE REMOVED FROM EXISTING POLES, RELOCATED AND SECURELY FASTENED TO THE SIGNAL SPAN WIRE OR WOOD POLE AS DIRECTED BY THE ENGINEER.
- 5 ANY TEMPORARY SIGNAL WITHIN AN EXISTING CLOSED LOOP TRAFFIC SIGNAL SYSTEM SHALL BE INTERCONNECTED TO THAT SYSTEM USING SIMILAR BRAND CONTROL EQUIPMENT.
- THE TEMPORARY TRAFFIC SIGNAL SHALL HAVE THE SIGNAL HEAD DISPLAYS. SIGNAL HEAD PLACEMENTS AND CONTROLLER PHASING MATCH THE EXISTING 6 TRAFFIC SIGNAL, AT THE TIME OF THE TURN ON, IF NO TRAFFIC STAGING IS IN PLACE OR WILL NOT BE STAGED ON THE DAY OF THE TURN ON.
- $\overline{7}$ CONTROLLER WITH STEEL BASE CABINET AND BATTERY BACK-UP CABINET SHALL BE MOUNTED ON A SERVICE ENTRANCE POLE.
- UN-INTERRUPTABLE POWER SUPPLY (UPS) SHALL BE INCLUDED IN "TEMPORARY (8) BRIDGE TRAFFIC SIGNAL INSTALLATION" PAY ITEM.
- 10 WOOD POLES INSTALLED BY THE TRAFFIC CONTRACTOR (SEE TEMPORARY 9 TRAFFIC SIGNAL PLANS FOR LOCATIONS).

TEMPORARY LIGHTING NOTES

- (1)TEMPORARY LUMINAIRE, SODIUM VAPOR, 400 WATT, 240V, HORIZONTAL-MOUNT, PHOTO-CELL, TYPE II DISTRIBUTION.
- TEMPORARY LIGHTING TO BE REMOVED AS DIRECTED BY 2 IDOT WHEN ROADWAY CONSTRUCTION IS COMPLETE.
- ALL SYSTEMS ARE TO BE REQUIRED TO REMAIN (3) OPERATIONAL DURING STAGED CONSTRUCTION.
- GROUND EVERY THIRD POLE WITH TEMPORARY (4)LUMINAIRE UNLESS NOTED OTHERWISE ON PLAN.
- (5) TEMPORARY POLES SHALL BE 60 FEET UNLESS OTHERWISE NOTED.

TEMPORARY TRAFFIC SIGNAL LEGEND


- COMBINATION LIGHTING AND TRAFFIC POLE MOUNTED ELECTRICAL SERVICE BOX
- TEMPORARY WOOD POLE NOMINAL 60 FT., \otimes CLASS 4
- TEMPORARY LED TRAFFIC SIGNAL HEAD, NUMBER OF SECTION AND DISPLAY AS REQUIRED
- TEMPORARY TRAFFIC SIGNAL SPAN WIRE, NUMBER OF CONDUCTORS AS REQUIRED
- TEMPORARY TRAFFIC CONTROLLER WITH UPS AND BOTTOM PLATE MOUNTED TO WOOD POLE
- TEMPORARY VIDEO DETECTOR

NOT TO SCALE

\$16\$1/6\$1/6\$1

TEMPORARY VIDEO DETECTION MOUNTING DETAIL

DESIGNED - SLV REVISED **TEMPORARY TRAFFIC** benesch Afred Banesch & Compar 1860 Weil St. Suite 222 Napeville, Illinois 60583 DRAWN - SLV REVISED STATE OF ILLINOIS US ROUTE 52 OVER J CHECKED - MJY, S REVISED **DEPARTMENT OF TRANSPORTATION** SCALE: 1" = 30' SHEET NO. 1 OF 2 DATE - 12/11/2012 REVISED



C SIGNAL PLAN		SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
JACKSON CREEK	852	18-B-4-R-2		WILL	44	15
	D-91-269-11			CONTRACT NO. 60N20		
STA. 448+82 TO STA. 455+90	FED. RC	AD DIST. NO.	ILLINOIS FED. A	ID PROJECT		