

CODE NO.	ITEM	UNIT	URBAN 100% STATE	
			CONSTR. CODE 0005	ROADWAY
			TOTAL QUANTITY	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	79	79
40600300	AGGREGATE (PRIME COAT)	TON	393	393
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4017	4017
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1667	1667
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8295	8295
42001300	PROTECTIVE COAT	SQ YD	79	79
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	97392	97392
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	450	450
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	100	100
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	580	580
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	640	640
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	960	960
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	672	672

CODE NO.	ITEM	UNIT	URBAN 100% STATE	
			CONSTR. CODE 0005	ROADWAY
			TOTAL QUANTITY	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12	12
60404950	FRAMES AND GRATES, TYPE 24	EACH	12	12
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	450	450
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8989	8989
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2546	2546
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80502	80502
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10410	10410
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	213	213

FILE NAME :	USER NAME : <i>mrooper</i>	DESIGNED - RG	REVISED -
#FILE# :		DRAWN - RG	REVISED -
	PLOT SCALE : 1/8" = 100.0000' / 1"	CHECKED - MGR	REVISED -
	PLOT DATE : 9/28/2012	DATE - 9/28/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 45 (OLD HALF DAY ROAD)
SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.J. RTE. 3502	SECTION 49-RS-6	COUNTY LAKE	TOTAL SHEETS 33	SHEET NO. 3
						CONTRACT NO. 60N31	
ILLINOIS FED. AID PROJECT							

Rev. 4-12-13

* - SPECIALTY ITEM

