

URBAN

URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	0005			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	23	23			
25200110	SODDING, SALT TOLERANT	SO YD	23	23			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34			
40600300	AGGREGATE (PRIME COAT)	TON	170	170			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	64	64			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	401	401			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4671	4671			
42001300	PROTECTIVE COAT	SO YD	27	27			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	426	426			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	256	256			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	171	171			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	953	953			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4			

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	0005			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
<del>70100450</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701201</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
<del>70100460</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701306</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
<del>70102620</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701501</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
<del>70102635</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701701</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1475	1475			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38783	38783			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	384	384			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	66	66			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	13936	13936			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38783	38783			

\* SPECIALTY ITEMS

FILE NAME: USER NAME: 11/11/2013

DESIGNED: DRAWN: CHECKED: DATE:

REVISED: REVISED: REVISED: REVISED:

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES F.A.P. 330/ US 45 (LA GRANGE RD.)--SAGER RD. TO STUENKAL RD. SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330 SECTION 104-RS-10 COUNTY WILL TOTAL SHEETS 20 SHEET NO. 3 CONTRACT NO. 60N32

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

Rev.