


IL 53 (INDEPENDENCE RD) EXISTING TYPICAL SECTION STA. 60+00 TO STA. 73+67 STA. 114+53 TO STA. 127+20

NOTE: CLASS D PATCHES, 15 INCHES NB & SB OUTSIDE LANES (STA. 4+58 TO STA. 149+04)

> CLASS D PATCHES, 11 INCHES INSIDE LANES INCLUDING TURN LANES (STA. 4+58 TO STA. 206+73



IL 53 (INDEPENDENCE RD) PROPOSED TYPICAL SECTION STA. 60+00 TO STA. 73+67 STA. 114+53 TO STA. 127+20

NOTE:

CLASS D PATCHES, 15 INCHES NB & SB OUTSIDE LANES (STA. 4+58 TO STA. 149+04)

CLASS D PATCHES, 11 INCHES INSIDE LANES INCLUDING TURN LANES (STA. 4+58 TO STA. 206+73

LEGEND

- EXISTING HMA RESURFACING, ± 6.50
- EXISTING P.C. CONCRETE PAVEMENT, (9"-7"-9")
- EXISTING P.C. CONCRETE BASE COURSE, ± 9"
- 4 EXISTING MOUNTABLE MEDIAN WITH CURB & GUTTER TYPE M-2.12
- EXISTING CONCRETE BARRIER MEDIAN, TYPE B-12.12
- 6 EXISTING COMB. CONC. C&G, TYPE B-6.24
- EXISTING BITUMONOUS SHOULDER, 8"
- EXISTING HMA BASE COURSE, ± 11"
- EXISTING AGGREGARE SHOULDER, TYPE B, 8"
- PROPOSED HMA SURFACE REMOVAL, 2-1/2"
- PROPOSED HMA SURFACE REMOVAL, 1-1/2"
- PROPOSED PCC SURFACE REMOVAL, 1"
- PROPOSED POLYMERIZED LEVELING BINDER
- (MACHINE METHOD), IL-4.75, N50, 3/4"
- PROPOSED POLYMERIZED HMA SURFACE COURSE, (14) MIX "F", N90, 1-3/4-"
- *(15) PROPOSED COMB. CONC. C&G REMOVAL AND REPLACEMENT
- PROPOSED AGGREGARE WEDGE SHOULDER, TYPE B
- PROPOSED GRADING AND SHAPING SHOULDERS

NOTE:

SCALE:

- * LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER
- "THE CONTRACTOR SHALL MILL FIRST PRIOR TO PATCHING".

FILE NAME =	USER NAME = galbanjr	DESIGNED	-	REVISED	-
c:\pw_work\pwidot\galbanjr\d0249519\D131	ll-sht-plan.dgn	DRAWN	-	REVISED	-
	PLOT SCALE = 100.0000 '/ in.	CHECKED	-	REVISED	-
	PLOT DATE = 8/20/2012	DATE	-	REVISED	-

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

IL 53 (N. INDEPENDENCE BLVD.)			SECTION	COUNTY	TOTAL SHEETS	SHEE1
EXISTING AND PROPOSED TYPICAL	SECTIONS	112	MY-RS-2	WILL	35	8
	SECTIONS			CONTRACT	NO. 6	ON44
CHEET NO OF CHEETS CTA	TO STA	THE THORE SER. AND DROUGHT				