

60 04

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	COOK CO 0005 100% STATE	DUPAGE CO 0005 100% STATE	DUPAGE CO 0005 65% STATE BENSENVILLE 35%	DUPAGE CO 0005 100% BENSENVILLE
20200100	EARTH EXCAVATION	CU YD	323		323		
20101000	TEMPORARY FENCE	FOOT	1200	600	600		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6057	2477	3580		
28100105	STONERIPRAP, CLASS A3	SQ YD	11		11		
20400800	FURNISHED EXCAVATION	CU YD	221		221		
20800150	TRENCH BACKFILL	CU YD	95		95		
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SO YD	16,580	7371	9479		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	5713		5713		
21400100	GRADING AND SHAPING DITCHES	FOOT	1400		1400		
25000210	SEEDING, CLASS 2A	ACRE	4.63	1.52	3.11		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	420	137	283		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	420	137	283		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	420	137	283		
25100630	EROSION CONTROL BLANKET	SO YD	22,564	7371	15,193		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	118		118		
28000305	TEMPORARY DITCH CHECKS	FOOT	682	15	667		
28000400	PERIMETER EROSION BARRIER	FOOT	1438		1438		

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	COOK CO 0005 100% STATE	DUPAGE CO 0005 100% STATE	DUPAGE CO 0031 65% STATE BENSENVILLE 35%	DUPAGE CO 0031 100% BENSENVILLE
28000510	INLET FILTERS	EACH	40	9	31		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1262		1262		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20		20		
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	1139		1139		
35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SQ YD	122		122		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	185	80	105		
X4060120	NON-TRACKING BITUMINOUS MATERIALS (PRIME COAT)	POUND	155,575	66,952	88,623		
40600300	AGGREGATE (PRIME COAT)	TON	926	401	525		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	695	301	394		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	12813	5524	7289		
40600895	CONSTRUCTING TEST STRIP	EACH	3	1.5	1.5		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1466	806	660		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	22289	9858	12431		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3995	1460	2535		

FILE NAME *	USER NAME * reitchebach1	DESIGNED -	REVISED -
DRAWN -	CHECKED -	DATE -	REVISED -
PLOT SCALE * 100,000' / 1"	PLOT DATE * 2/15/2013		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 83
IL 19 (IRVING PARK RD.) TO IL 72 (DAKTON ST.)
SUMMARY OF QUANTITIES

F.A.P. RTE. 344	SECTION 540R-RS-2	COUNTY DUPAGE&COOK	TOTAL SHEETS 49	SHEET NO. 3
CONTRACT NO. 60N49				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 4-10-13

Rev.