

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		COOK CO 0005	DUPAGE CO 0005	DUPAGE CO 0005 65% STATE BENSENVILLE 35%	DUPAGE CO 0005 100% BENSENVILLE
42001300	PROTECTIVE COAT	SO YD	12,774	5865	6909		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	223327	97027	126300		
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	20		20		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10,847	2871	7976		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	7104	3232	3872		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	580	414	166		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	850	218	632		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	612	224	388		
50105220	PIPE CULVERT REMOVAL	FOOT	99		99		
54261318	CONCRETE END SECTION, STANDARD 542001, 18" 1:3	EACH	1		1		
54213663	PREGAST REINFORCED CONCRETE FLARED END	EACH	1		1		
	SECTIONS 18"						
550A0070	STORM SEWERS, CLASS A, TYPE I 15"	FOOT	100		100		
550A0090	STORM SEWERS, CLASS A, TYPE I 18"	FOOT	715		715		
550A0120	STORM SEWERS, CLASS A, TYPE I 24"	FOOT	300		300		
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	7		7		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		COOK CO 0005	DUPAGE CO 0005	DUPAGE CO 0005 65% STATE BENSENVILLE 35%	DUPAGE CO 0005 100% BENSENVILLE
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1		1		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	20	13	7		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	2	2		
60262700	INLETS TO BE RECONSTRUCTED	EACH	4	2	2		
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	5	5		
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	5	5		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2203		2203		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8485	2706	5779		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	1785	840	945		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5	0.5		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5		

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		IL ROUTE 83 IL 19 (IRVING PARK RD.) TO IL 72 (OAKTON ST.) SUMMARY OF QUANTITIES		P.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN	REVISED					344	54OR-RS-2	DUPAGE&COOK	49	4
		CHECKED	REVISED							CONTRACT NO.	60N49	
		DATE	REVISED					SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT

Rev.