

SUMMARY OF QUANTITIES			URBAN 100'L STATE		CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0005	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	20	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	77	77	
40600300	AGGREGATE (PRIME COAT)	TON	381	381	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	143	143	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3996	3996	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	697	697	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	243	243	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIK "F", N90	TON	9324	9324	
42001300	PROTECTIVE COAT	SO YD	100	100	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	95139	95139	
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SO YD	2165	2165	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	20	20	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	660	660	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	820	820	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	665	665	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	553	553	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15	
60404950	FRAMES AND GRATES, TYPE 24	EACH	15	15	
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	5	5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	26632	26632	

27 * SPECIALTY ITEMS

SUMMARY OF QUANTITIES			URBAN 100'L STATE		CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0005	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	896	896	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	86820	86820	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3011	3011	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1454	1454	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	550	550	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SAFT	8878	8878	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	896	896	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	86820	86820	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3011	3011	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1454	1454	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	550	550	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	618	618	
78300100	PAVEMENT MARKING REMOVAL	SO FT	9570	9570	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	618	618	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2581	2581	
X2020110	GRADING AND SHAPING SHOULDERS	UNITS	550	550	
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	150	150	
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	150	150	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	318	318	
Z0004562	COMBINATION CURB AND GUTTER REMOVE AND REPLACE CONCRETE	FOOT	300	300	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701330	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
20076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500	

28

0042

Rev. 4-8-13

Rev.