


PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE	
				ROADWAY 0005	URBAN
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	114	114	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	429	429	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	167	167	
21400100	GRADING AND SHAPING DITCHES	FOOT	1,544	1,544	
25000210	SEEDING, CLASS 2A	ACRE	0.53	0.53	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	48	48	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	48	48	
25100630	EROSION CONTROL BLANKET	SO YD	2,573	2,573	
25200110	SODDING, SALT TOLERANT	SO YD	167	167	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	57	57	
40600300	AGGREGATE (PRIME COAT)	TON	284	284	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	103	103	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	303	303	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,845	3,845	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,089	8,089	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	71,037	71,037	

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE	
				ROADWAY 0005	URBAN
42101300	PROTECTIVE COAT	SO YD	333	333	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	9	9	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	2,300	2,300	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	250	250	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	2,700	2,700	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	685	685	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	30	30	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9,748	9,748	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	680	680	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	97,485	97,485	



USER NAME - 1485	DESIGNED - EF	REVISED -
	DRAWN - EF	REVISED -
PLOT SCALE - 100.0000 / 1"	CHECKED - RS	REVISED -
PLOT DATE - 12/11/2012	DATE - 12-20-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 173 (ROSECRANS RD) N. ORCHARD STREET TO DEEP LAKE ROAD
SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 135-R5-3	COUNTY LAKE	TOTAL SHEETS 25	SHEET NO. 3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60NG1	