

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	239	239			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11516	11516			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1441	1441			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	556	556			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	979	979			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8509	8509			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	239	239			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11516	11516			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1441	1441			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1756	1756			
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	979	979			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	314	314			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	252	252			
88600600	DETECTOR LOOP REPLACEMENT	FOOT	715	715			
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	11			
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
0042	TRAINees - TRAINING PROGRAM GRADUATE	HOUR	500	500			
0042	SPECIALTY ITEMS						

© 2007/6/6/04 TRAINees - TRAINING PROGRAM GRADUATE HOUR 500 500

© 0042

Rev. 4-8-13