

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	38	38				
25200110	SODDING, SALT TOLERANT	SO YD	38	38				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34				
40600300	AGGREGATE (PRIME COAT)	TON	158	158				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	63	63				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1727	1727				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	442	442				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	148	148				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3515	3515				
42001300	PROTECTIVE COAT	SO YD	55	55				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	38	38				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	38825	38825				
44000600	SIDEWALK REMOVAL	SO FT	38	38				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	875	875				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	27178	27178				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	580	580				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	85	85				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	55	55				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9813	9813				