

SUMMARY OF QUANTITIES

**URBAN
100% STATE**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				URBAN 100% STATE	ROADWAY 0005
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38	
40600300	AGGREGATE (PRIME COAT)	TON	228	228	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	29	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,246	2,246	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	163	163	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,083	5,083	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	56,917	56,917	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	55	55	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	290	290	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	345	345	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	210	210	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	413	413	
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,807	14,807	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109,686	109,686	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,996	4,996	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,706	1,706	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	672	672	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	42,111	42,111	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	54,843	54,843	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,103	2,103	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	395	395	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	853	853	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	336	336	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	384	384	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0005	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	384	384	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	908	908	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	250	250	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4	

* SPECIALTY ITEMS

FILE NAME: S:\p\proj\212012\05_0021\4602\11115\03\032012\03\summary.qxd



USER NAME: dplon12724	DESIGNED: DLP	REVISED: -
DRAWN: STANTEC	CHECKED: TMH	REVISED: -
DATE: 12/12/2012		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 120 ROADWAY RESURFACING
SUMMARY OF QUANTITIES**

F.A.P. RTE. 333	SECTION 16-RS-9	COUNTY LAKE	TOTAL SHEETS 21	SHEET NO. 3
SCALE: 5/8" = 1' IN.			CONTRACT NO. 60N79	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				