

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	169	169			
25200110	SODDING, SALT TOLERANT	SO YD	169	169			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28			
40600300	AGGREGATE (PRIME COAT)	TON	139	139			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52	52			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4, 75, N50	TON	1431	1431			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	177	177			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2912	2912			
42001300	PROTECTIVE COAT	SO YD	1,618	1,618			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	134	134			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	207	207			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34678	34678			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	146	146			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5575	5575			
44000600	SIDEWALK REMOVAL	SQ FT	207	207			
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	33	33			
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	232	232			

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005			
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	58	58			
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	30	30			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	32	32			
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	6	6			
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	11	11			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	16	16			
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12 (MODIFIED)	FOOT	5575	5575			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5769	5769			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	328	328			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13756	13756			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1344	1344			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	735	735			

FILE NAME =	USER NAME = pyzanoski10	DESIGNED -	REVISED -
CLP:\work\p4100\pyzanoski10\0312\1251712.dwg		DRAWN -	REVISED -
PLOT SCALE = 100,000' / 1"		CHECKED -	REVISED -
PLOT DATE = 2/6/2013		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	571W-R5-2	COOK	22	3
CONTRACT NO. 60V10				

Rev. 4-11-13