

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	169	169				
25200110	SODDING, SALT TOLERANT	SO YD	169	169				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28				
40600300	AGGREGATE (PRIME COAT)	TON	139	139				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52	52				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4, 75, N50	TON	1431	1431				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	177	177				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2912	2912				
42001300	PROTECTIVE COAT	SO YD	1,618	1,618				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	134	134				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	207	207				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34678	34678				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	146	146				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5575	5575				
44000600	SIDEWALK REMOVAL	SQ FT	207	207				
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	33	33				
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	232	232				

URBAN  
100%  
STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005				
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	58	58				
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	30	30				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	32	32				
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	6	6				
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	11	11				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	16	16				
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12 (MODIFIED)	FOOT	5575	5575				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5769	5769				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	328	328				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13756	13756				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1344	1344				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	735	735				

URBAN  
100%  
STATE

FILE NAME =	USER NAME = pyzanoski10	DESIGNED -	REVISED -
CLP:\work\p410\pyzanoski10\0312\1251712.dwg		DRAWN -	REVISED -
PLOT SCALE = 100,000' / 1"		CHECKED -	REVISED -
PLOT DATE = 2/6/2013		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	571W-R5-2	COOK	22	3
CONTRACT NO. 60V10				

Rev. 4-11-13

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	0005				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1097	1097				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	230	230				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4173	4173				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	328	328				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13756	13756				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1344	1344				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	735	735				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1097	1097				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230	230				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	650	650				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	606	606				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1405	1405				
* 6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	41	41				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SO YD	12	12				
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1000	1000				
<del>Z0018100</del>	<del>DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)</del>	<del>EACH</del>	<del>11</del>	<del>11</del>				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	0005				
<del>Z0018300</del>	<del>DRAINAGE STRUCTURE REPAIR</del>	<del>EACH</del>	<del>16</del>	<del>16</del>				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	205.6	205.6				

FILE NAME	USER NAME	DESIGNED	REVISED
CDR:\work\1011015\1011015\1011015.dwg	gpr20042110	-	-
PLOT SCALE	CHECKED	DATE	REVISED
1/4" = 1'-0"	-	-	-
PLOT DATE	DATE		
2/6/2013	-		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	571W-R5-2	COOK	22	4
CONTRACT NO. 60V10				

\* Specialty Items

Rev. 4-11-13