

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	169	169					44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	58	58						
25200110	SODDING, SALT TOLERANT	SO YD	169	169					44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	30	30						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28					60250200	CATCH BASINS TO BE ADJUSTED	EACH	32	32						
40600300	AGGREGATE (PRIME COAT)	TON	139	139					60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	6	6						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52	52					60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	11	11						
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1431	1431					60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	5575	5575						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	177	177					67100100	MOBILIZATION	L SUM	1	1						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2912	2912					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	134	134					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	207	207					70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34678	34678					70300100	SHORT TERM PAVEMENT MARKING	FOOT	5769	5769						
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	146	146					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	328	328						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5575	5575					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13756	13756						
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	33	33					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1344	1344						
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	232	232					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	735	735						

URBAN
100%
STATE

URBAN
100%
STATE

FILE NAME * c:\pwr\work\100101\pwr\2004\11\04\03\12\09\05\12-sht-1.dwg	USER NAME * pyrczanowski	DESIGNED -	REVISED -
PLOT SCALE * 100000 1/16"	CHECKED -	REVISOR -	REVISOR -
PLOT DATE * 2/16/2013	DATE -	REVISOR -	REVISOR -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE. 350	SECTION 571W-RS-2	COUNTY COOK	TOTAL SHEETS 22	SHEET NO. 3
CONTRACT NO. 60V10				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				