

MILE MARKER	DIRECTION	LANE	LENGTH (FT)	WDTH (FT)	PATCH AREA				SAWCUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ YD)	PCC SURFACE REMOVAL (VARIABLE DEPTH) X4400100 (SQ YD)	POLYMER CONCRETE Z0041895 (CU FT)
					TYPE I (SQ YD)	TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)					
45-00 TO 45-11	Reversible Lanes	2	3	0.5					5.0			0.2	0.5
45-00 TO 45-11	Going South	2	1	1					3.0				0.2
45-00 TO 45-11		2	8	6		5.3			55.0		5.3		
45-15		1	12	12			16.0		91.0		16.0		
45-15		2	12	12			16.0		91.0		16.0		
45-15		1	6	6	4.0				49.0		4.0		
45-15		1	12	6		8.0			67.0		8.0		
45-66		1	6	12		8.0			73.0		8.0		
45-66		2	6	12		8.0			73.0		8.0		
45-66		2	6	12		8.0			73.0		8.0		
45-76		2	14	0.7					16.0			0.5	2.3
45-77		2	30	0.5					32.0	30		1.7	5.0
45-84		1	6	12		8.0			73.0		8.0		
45-84		2	6	12		8.0			73.0		8.0		
45-93		1	6	12		8.0			73.0		8.0		
45-93		2	6	12		8.0			73.0		8.0		
46-36		2	6	12		8.0			73.0		8.0		
46-55		1	6	12		8.0			73.0		8.0		
46-55		2	6	12		8.0			73.0		8.0		
46-55		2	6	12		8.0			73.0		8.0		
46-59		1	6	12		8.0			73.0		8.0		
46-59		2	6	12		8.0			73.0		8.0		
46-59		3	6	12		8.0			73.0		8.0		
46-59		4	6	12		8.0			73.0		8.0		
47-08		1	6	12		8.0			73.0		8.0		
47-08		2	6	12		8.0			73.0		8.0		
47-26		2	25	0.7					27.0	25		0.8	4.2
47-29		2	20	0.7					22.0	20		0.7	3.3
47-29		2	20	0.5					22.0	20		1.1	3.3
47-33		2	28	0.7					30.0	28		0.9	4.7
47-35 TO 47-47		2	180	1					182.0	180			30.0
47-60		2	26	0.5					28.0	26		1.4	4.3
47-67		2	30	1					32.0	30			5.0
47-67 TO 47-75		2	60	1					62.0	60			10.0
47-98 TO 48-04		2	80	0.7					82.0	80		2.7	13.3
48-04		2	20	0.5					22.0	20		1.1	3.3
48-04		2	20	1					22.0	20			3.3
48-12		2	5	1					7.0				0.8
48-12		2	10	0.5					12.0			0.6	1.7
48-27		1	6	12		8.0			73.0		8.0		
48-27		2	6	12		8.0			73.0		8.0		
48-38		2	20	0.5					22.0	20		1.1	3.3
48-49		2	6	12		8.0			73.0		8.0		
48-71		1	6	12		8.0			73.0		8.0		
48-91		1	6	12		8.0			73.0		8.0		
48-91 TO 48-94		2	6	12		8.0			73.0		8.0		
48-94 TO 49-01		2	60	0.5					62.0	60		3.3	10.0
49-01 TO 49-08		2	80	0.7					82.0	80		2.7	13.3
49-08 TO 49-12		2	25	0.5					27.0	25		1.4	4.2
49-12 TO 49-14		2	20	0.5					22.0	20		1.1	3.3
49-40		1	6	12		8.0			73.0		8.0		
49-51 TO 49-55		1	6	12		8.0			73.0		8.0		
49-80		2	30	0.5					32.0	30		1.7	5.0
SHEET TOTALS					4.0	213.3	32.0	0.0	3031.0	774.0	249.3	22.9	134.6
					SQ YD	SQ YD	SQ YD	SQ YD	FT	EACH	SQ YD	SQ YD	CU FT



USER NAME =	DESIGNED - RG	REVISED -
PLOT SCALE =	DRAWN - RG	REVISED -
PLOT DATE	CHECKED - MR	REVISED -
	DATE - DECEMBER 2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PATCHING LOCATIONS
REVERSIBLE LANES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2012-055BR	COOK	107	14
CONTRACT NO. 60V58				
ILLINOIS FED. AID PROJECT				