

901.FED.  
101.STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0004 URBAN	URBAN/ BRIDGE 0014 SN 016-2437	TRAFFIC SIGNALS 0021 URBAN
✓ * X0370032	CONDUIT IN TRENCH, 2" PVC, SCHEDULE 80 (CDOT)	FOOT	390			390
✓ * X0370033	UNDERGROUND CONDUIT, SCHEDULE 40 PVC, 2" DIAMETER, (CDOT)	FOOT	2,669			2,669
✓ * X0370034	PVC CONDUIT IN TRENCH, 3" (SCHEDULE 40) (CDOT)	FOOT	365			365
✓ * X0370035	PVC CONDUIT IN TRENCH, 3" (SCHEDULE 80) (CDOT)	FOOT	1,665			1,665
✓ * X0370036	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT, CHICAGO	LSUM	2			2
✓ * X0370037	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED (CDOT)	EACH	10			10
✓ * X0370038	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED (CDOT)	EACH	10			10
✓ * X0370039	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED (CDOT)	EACH	2			2
✓ * X0370040	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED (CDOT)	EACH	2			2
✓ * X0370041	TRAFFIC SIGNAL POST, ALUMINUM, 15 FT. (CDOT)	EACH	4			4
✓ * X0370042	VIDEO CABLE HARNESS (CDOT)	EACH	3			3
✓ * X0370043	VIDEO DETECTION CAMERA (CDOT)	EACH	4			4
✓ * X0370044	VIDEO DETECTION POWER SUPPLY (CDOT)	EACH	2			2
✓ * X0370045	VIDEO PROCESSOR CARD AND RACK (CDOT)	EACH	2			2

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com



\* Specialty Items

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - OC	REVISED -					94	2012-060-BR	COOK	285	21
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NA SHEET NO. 19 OF 19 SHEETS STA. TO STA.			CONTRACT NO. 60V61				
	PLOT DATE = 12/7/2012	DATE - 11/08/2012	REVISED -					ILLINOIS FED. AID PROJECT				

S:\312\05\_CCD\0169\61\_Sheet\0169\61-A1-1000.dgn