

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005					CODE NO	ITEM	UNIT		0005				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23					70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1				
40600300	AGGREGATE (PRIME COAT)	TON	112	112					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42	42					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, NS0	TON	1119	1119					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300100	SHORT TERM PAVEMENT MARKING	FOOT	1368	1368				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	432	432					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	546	546				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2610	2610					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21329	21329				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	27838	27838					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2067	2067				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	227	227					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	484	484				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	160	160					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	100	100				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	314	314					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	228	228				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	118	118					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	546	546				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21329	21329			*	SPECIALTY ITEMS
67100100	MOBILIZATION	L SUM	1	1													