

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003	0021
				URBAN	URBAN
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	88	88	
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	710	710	
20101100	TREE TRUNK PROTECTION	EACH	10	10	
20101200	TREE ROOT PRUNING	EACH	10	10	
20200100	EARTH EXCAVATION	CU YD	7,983	7,983	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	816	816	
20400800	FURNISHED EXCAVATION	CU YD	200	200	
20800150	TRENCH BACKFILL	CU YD	423	423	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,080	3,080	
* 21101615	TOPSOIL FURNISH AND PLACE 4"	SQ YD	20,505	20,505	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	255	255	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	255	255	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	255	255	
* 25100630	EROSION CONTROL BLANKET	SQ YD	20,505	20,505	
* 25200110	SODDING, SALT TOLERANT	SQ YD	20,505	20,505	

* SPECIALTY ITEMS
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: # 104-001322
 CLIENT: # 104-001322
 DATE PLOTTED: 2/13/2013 12:36:24 PM
 FILE NAME: 635_sump.dgn
 PLOT DRIVER: pdf_writer
 PLOT TABLE: # 104-001322.tbl



USER NAME = spernal	DESIGNED - DCJ	REVISED -
PLOT SCALE =	DRAWN - SMP	REVISED -
PLOT DATE = 2/13/2013	CHECKED - TEH	REVISED -
	DATE - 2/5/13	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 1 OF 13 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4087	98-00024-00-WR	MCHENRY	115	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 63532	