

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003	0021
				URBAN	URBAN
* 25200200	SUPPLEMENTAL WATERING	UNIT	185	185	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	424	424	
28000305	TEMPORARY DITCH CHECKS	FOOT	90	90	
28000400	PERMITER EROSION BARRIER	FOOT	2,170	2,170	
28000510	INLET FILTERS	EACH	49	49	
28100105	STONE RIPRAP, CLASS A3	SQ YD	28	28	
28200200	FILTER FABRIC	SQ YD	39	39	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	784	784	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	11,045	11,045	
31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	4,615	4,615	
31101400	SUB BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1,720	1,720	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	3,005	3,005	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	915	915	
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	2,345	2,345	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,139	2,139	

* SPECIALTY ITEMS
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: # 194-001322
 CLIENT: MCHENRY COUNTY
 DATE PLOTTED: 2/13/2013 12:58:27 PM
 PLOT SCALE: 1" = 100'
 PLOT ORIGIN: 0,0
 PEN TABLE: Standard-Trans.plt



HRGreen.com
 Illinois Professional Design Firm
 # 194-001322

USER NAME = aparnal	DESIGNED - DCJ	REVISED -
PLOT SCALE =	DRAWN - SMP	REVISED -
PLOT DATE = 2/13/2013	CHECKED - TEH	REVISED -
	DATE - 2/5/13	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 13 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4087	98-00024-00-WR	MCHENRY	115	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63532	