

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003 URBAN	0021 URBAN
40600300	AGGREGATE (PRIME COAT)	TON	88	88	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	8	8	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	105	105	
40600895	CONSTRUCTION TEST STRIP	EACH	4	4	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	90	90	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	96	96	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,779	1,779	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	978	978	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,358	1,358	
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	6,770	6,770	
42001300	PROTECTIVE COAT	SQ YD	4,461	4,461	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	50	50	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	24,349	24,349	
42400800	DETECTABLE WARNINGS	SQ FT	399	399	
44000100	PAVEMENT REMOVAL	SQ YD	6,375	6,375	

\* SPECIALTY ITEMS  
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen.com  
 PROJECT CONTACT: #164-001322  
 CLIENT: #164-001322  
 DATE PLOTTED: 2/13/2013 12:26:37 PM  
 FILE NAME: 635332.dwg  
 PLOT ORIGIN: 0,0  
 PLOT SCALE: 1/8"=1'-0"  
 PLOT DATE: 2/13/2013



USER NAME = sperral	DESIGNED - DCJ	REVISED -
PLDT SCALE =	DRAWN - SMP	REVISED -
PLDT DATE = 2/13/2013	CHECKED - TEH	REVISED -
	DATE - 2/5/13	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	TOTAL SHEETS
	3	OF	13

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4087	98-00024-00-WR	MCHENRY	115	6
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		CONTRACT NO. 63532	