

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003	0021
				URBAN	URBAN
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	6,577	6,577	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3,503	3,503	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,648	2,648	
44000600	SIDEWALK REMOVAL	SQ FT	14,905	14,905	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,581	1,581	
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	90	90	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	90	90	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	235	235	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	200	200	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5,010	5,010	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,031	1,031	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,135	1,135	
542A5470	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	92	92	
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	138	138	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	162	162	

* SPECIALTY ITEMS
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: #184-001322
 CLIENT: #184-001322
 DATE PLOTTED: 2/21/2013 5:17:02 PM
 FILE NAME: 638_sump.dgn
 PLOT DRIVER: pdfplot
 PEN TABLE: s:\pender-trans.tbl



USER NAME = spernal	DESIGNED - DCJ	REVISED -
PLOT SCALE =	DRAWN - SMP	REVISED -
PLOT DATE = 2/21/2013	CHECKED - TEH	REVISED -
	DATE - 2/5/13	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 13 SHEETS STA. TO STA.

F.A.I.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4087	98-00024-00-WR	MCHENRY	115	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63532	