


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003 URBAN	0021 URBAN
55100500	STORM SEWER REMOVAL 12"	FOOT	1,003	1,003	
55100700	STORM SEWER REMOVAL 15"	FOOT	1,282	1282	
55100900	STORM SEWER REMOVAL 18"	FOOT	372	372	
55101200	STORM SEWER REMOVAL 24"	FOOT	347	347	
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	50	50	
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	150	150	
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	8	8	
* 56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	2	2	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5	5	
60201105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1	
60201340	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 24 FRAME AND GRATE	EACH	8	8	
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	5	5	
60218300	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10	

\* SPECIALTY ITEMS  
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen.com  
 PROJECT CONTACT: #104-001322  
 CLIENT: #104-001322  
 DATE PLOTTED: 2/21/2013 3:08:00 PM  
 FILE NAME: 635.sum.plt  
 PLOT DRIVERS: pdf2400  
 PEN TABLE: Standard-Frame.tbl

 HRGreen.com #104-001322	USER NAME = sperral	DESIGNED - DCJ	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - SMP	REVISED -			4087	98-00024-00-WR	MCHENRY	115	9
PLOT DATE = 2/21/2013	CHECKED - TEH	DATE - 2/5/13	REVISED -	SCALE:	SHEET NO. 6 OF 13 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 63532