

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% LOCAL ROADWAY	80% FEDERAL 20% LOCAL SIGNALS
				0003 URBAN	0021 URBAN
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	185.0		185.0
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	82.0		82.0
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	245.0		245.0
* 81400100	HANDHOLE	EACH	5		5
* 81400200	HEAVY-DUTY HANDHOLE	EACH	2		2
* 81400300	DOUBLE HANDHOLE	EACH	1		1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,103.0		2,103.0
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,101.5		1,101.5
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,361.0		1,361.0
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,127.5		1,127.5
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	125.5		125.5
* 87301900	ELECTRICAL CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6.1C	FOOT	996.5		996.5
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1		1
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2

* SPECIALTY ITEMS
 Δ CONSTRUCTION CODE 0042

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 3/25/2013 2:47:32 PM
 FILE NAME: 6356.mxd
 PLOT DRIVER: pdfLyrwrt
 PEN TABLE: penne.standards-trans - Copy.tbl



HRGreen.com
 Whole Professional Design Firm
 #184-001322

USER NAME = spurnal	DESIGNED - DCJ	REVISED -
DRAWN - SMP	CHECKED - TEH	REVISED -
PLOT SCALE =	DATE - 2/5/13	REVISED -
PLOT DATE = 3/25/2013		

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 10 OF 13 SHEETS	STA.	TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4087	98-00024-00-WR	MCHENRY	115	13
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 63532	