

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				HPP FUNDS									
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	100% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	ROADWAY 0003 URBAN		
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	113				113						
* Z0028450	GEOTEXTILE FABRIC FOR RAILROAD CROSSING	SO YD	476	476									
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	226	226									
• Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1					1					
• Z0033058	POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)	EACH	4					4					
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130		130								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1	1									
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	326	326									
Z0062456	TEMPORARY PAVEMENT	SO YD	3111	3111									
Z0062458	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TON	29	29									
* Z0069700	SUB-BALLAST	CU YD	1167	1167									
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	9451	9451									
Z0073346	SLEEPER SLAB	SO YD	62	62									
Z0073500	TEMPORARY SUPPORT SYSTEM	LSUM	1			1							

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\DI63598-shr-eq-28.dgn	DRAWN - TMB	REVISED -
USER NAME = toddblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 20 OF 21 SHEETS STA. TO STA.

F.A.P. RTE. 361	SECTION 06-00214-18-RP	COUNTY KANE	TOTAL SHEETS 451	SHEET NO. 24
CONTRACT NO. 63598				ILLINOIS FED. AID PROJECT