

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0008	0021	0040	0042
				ROADWAY	BRIDGE SN 056-8010	TRAFFIC SIGNALS	RETAINING WALLS	TRAINEES
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	3451	3451				
42001300	PROTECTIVE COAT	SQ YD	7034	7034				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	370	370				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1876	1876				
42400800	DETECTABLE WARNINGS	SQ FT	132	132				
44000100	PAVEMENT REMOVAL	SQ YD	4221	4221				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	518	518				
44000500	COMBINATION CURB AND CUTTER REMOVAL	FOOT	3283	3283				
44000600	SIDEWALK REMOVAL	SQ FT	707	707				
44004250	PAVED SHOULDER REMOVAL	SQ YD	71	71				
50200100	STRUCTURE EXCAVATION	CU YD	9				9	
50300225	CONCRETE STRUCTURES	CU YD	75.5		75.5			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	277		277			
50300260	BRIDGE DECK GROOVING	SQ YD	679		679			
50300300	PROTECTIVE COAT	SQ YD	768		768			
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	528		528			
50800205	REINFORCEMENT BARS, EPOXY COATED	POLND	69280		69280			
50800515	BAR SPLICERS	EACH	86		86			
Δ 50901720	BICYCLE RAILING	FOOT	66		66			
Δ 50901750	PARAPET RAILING	FOOT	62		62			
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	920		920			
51202305	DRIVING PILES	FOOT	920		920			
51203200	TEST PILE METAL SHELLS	EACH	2		2			
51500100	NAME PLATES	EACH	1		1			
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	73	73				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2 4	2 4	Δ			
Δ 54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1				
Δ 54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2				
54215550	METAL END SECTIONS 15"	EACH	1	1				

• INDICATES SPECIAL PROVISION
Δ SPECIALTY ITEMS

FILE NAME ...N2473,930,82.dgn	USER NAME f.bas	DESIGNED BAS	REVISED 4/11/2013 Δ	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: NONE	SHEET NO. 2 OF 7 SHEETS	STA.	TO STA.	ADDENDUM Δ REV. 4/11/2013 CTB			
	PLOT SCALE = 1/8" = 1' - 0"	DRAWN BAS	REVISED							F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS
	PLOT DATE 4/15/2013	CHECKED GAD	REVISED							4068	07-0031-00-PV	McHENRY	167
		DATE 10/22/12	REVISED									CONTRACT NO. 63743	SHEET NO. 6