



RESTORATION OF WORK AREA.

RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE COST OF
THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND
BACKFILE, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL PADAWAY
SURFACES SUCH AS SHOULDER, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE
REPLACED IN KIND, ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN
APPROVED SALT TOLERANT SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE
SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

NOTE: THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME =	USER NAME R bas	DESIGNED - BRD	REVISED -		INTERCONNECT PLAN	F.A.U. SECTION COUNTY TOTAL SHEET
\2473_TS.:08_Interconnect_Plan_3.dgn		DRAWN - BRD	REVISED -	STATE OF ILLINOIS	IL ROUTE 47	4068 07-0031-00-PV McHENRY 167 76
	PLOT SCALE = 50.00000 '/ in.	CHECKED - JUE	REVISED -	DEPARTMENT OF TRANSPORTATION	(KREUTZER ROAD TO MAIN STREET)	CONTRACT NO 63743
	PLOT DATE = 10/18/2012	DATE - 10/22/12	REVISED -		SCALE: 1" = 50' SHEET NO. 3 OF 4 SHEETS STA. TO STA.	FED, ROAD DIST, NC. 1 ILLINOIS FED, AID PROJECT XXX