

SUMMARY OF QUANTITIES

| CODE NUMBER | PAY ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE | | | |
|-------------|---|-------|----------------|------------------------|-------|--------|-------------------|
| | | | | ROADWAY | | SAFETY | NON PARTICIPATING |
| | | | | 0003 | | 0021 | |
| STU | STE | STU | | | | | |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 722 | - | 722 | - | - |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 482 | - | 482 | - | - |
| 40701871 | HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2" | SQ YD | 22,456 | 22,456 | - | - | - |
| 42000211 | PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2" (JOINTED) | SQ YD | 2,385 | 2,385 | - | - | - |
| 42001300 | PROTECTIVE COAT | SQ YD | 11,336 | 11,336 | - | - | - |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 668 | 668 | - | - | - |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 1,495 | 1,495 | - | - | - |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 14,413 | 14,413 | - | - | - |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 620 | 290 | 330 | - | - |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 29,586 | 29,586 | - | - | - |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 2,426 | 2,426 | - | - | - |
| 44000300 | CURB REMOVAL | FOOT | 77 | 77 | - | - | - |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 4,748 | 4,748 | - | - | - |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 15,628 | 10,802 | 4,826 | - | - |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 42 | 42 | - | - | - |
| 50100300 | REMOVAL OF EXISTING STRUCTURES NO. 1 | EACH | 1 | 1 | - | - | - |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 597 | 597 | - | - | - |
| 50300225 | CONCRETE STRUCTURES | CU YD | 179.2 | 179.2 | - | - | - |
| 50300285 | FORM LINER TEXTURED SURFACE | SQ FT | 1,204 | 1,204 | - | - | - |
| 50800105 | REINFORCEMENT BARS | POUND | 12,350 | 12,350 | - | - | - |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 900 | 900 | - | - | - |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 3 | 3 | - | - | - |
| 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | EACH | 1 | 1 | - | - | - |
| 550A2320 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12" | FOOT | 2,475 | 2,475 | - | - | - |
| 550A2330 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15" | FOOT | 1,058 | 1,058 | - | - | - |
| 550A2340 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18" | FOOT | 592 | 592 | - | - | - |
| 550A2360 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24" | FOOT | 1,052 | 1,052 | - | - | - |
| 550A2520 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12" | FOOT | 52 | 52 | - | - | - |
| 550A2530 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15" | FOOT | 127 | 127 | - | - | - |
| 550A2560 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24" | FOOT | 407 | 407 | - | - | - |

* INDICATES SPECIALTY ITEM

CONTRACT NO. 95-00049-00-PV
 DRAWN BY: UKR
 CHECKED BY: RWL
 DATE: 06/20/12
 DESIGNED BY: DJS
 REVISIONS: PER IDOT 10/19/12
 FILE: J10994-50TY.shp
 PROJECT: 95-00049-00-PV
 COUNTY: KANE
 SHEETS: 138 OF 140
 CONTRACT NO. 63745
 FEDERAL AID PROJECT NO. M-6003 10951



| | |
|-----------------|-----------------------------|
| DESIGNED - DJS | REVISED - PER IDOT 10/19/12 |
| DRAWN - UKR | REVISED - |
| CHECKED - RWL | REVISED - |
| DATE - 06/20/12 | FILE - J10994-50TY.shp |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

| | | | | |
|--|----------------|--------|--------------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 4006 | 95-00049-00-PV | KANE | 138 | 4 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-6003 10951 | | | CONTRACT NO. 63745 | |