

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY		SAFETY	NON PARTICIPATING
				0003		0021	
STU	STE	STU					
60402210	GRATES, TYPE 8	EACH	1	1	-	-	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	-	-	-
60500040	REMOVING MANHOLES	EACH	1	1	-	-	-
60500050	REMOVING CATCH BASINS	EACH	8	8	-	-	-
60500060	REMOVING INLETS	EACH	7	7	-	-	-
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,046	1,046	-	-	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	14,442	14,442	-	-	-
* 60900515	CONCRETE THRUST BLOCKS	EACH	86	-	-	-	86
66300105	CALCIUM CHLORIDE APPLIED	TON	17	17	-	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-	-
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5,501	5,501	-	-	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42,762	42,762	-	-	-
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,657	1,657	-	-	-
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	866	866	-	-	-
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	635	635	-	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,640	2,640	-	-	-
72000100	SIGN PANEL - TYPE 1	SQ FT	499	499	-	-	-
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	60	60	-	-	-
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	7	7	-	-	-
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1,258	1,258	-	-	-
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,038	9,038	-	-	-
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,657	1,471	186	-	-
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	866	-	866	-	-
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	360	360	-	-	-
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,550	1,550	-	-	-
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,090	2,090	-	-	-
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	-	-	2	-
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	2	-	-	2	-
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	841	-	-	841	-
* 81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	5,623	-	-	5,623	-

* INDICATES SPECIALTY ITEM

CONTRACT NO. 2012 BY EAST CO. & WOODMAN, INC. 11/20/12
 DRAWN BY: UKB 11/20/12
 CHECKED BY: RWL 11/20/12
 DATE: 06/20/12
 FILE: 110994-SQTY.srt
 PROJECT: 95-00049-CO-FV
 COUNTY: KANE
 SHEETS: 138
 SHEET NO.: 5
 CONTRACT NO.: 63745
 FEDERAL AID PROJECT: M-8003 (095)



DESIGNED -	DJS	REVISED -	PER IDOT 10/19/12
DRAWN -	UKB	REVISED	
CHECKED -	RWL	REVISED	
DATE -	06/20/12	FILE -	110994-SQTY.srt

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: STA. 10 STA.

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4006	95-00049-CO-FV	KANE	138	5
FED. ROAD DIST. NO. 1 ILLINOIS			FED. AID PROJECT M-8003 (095)	
			CONTRACT NO. 63745	