

**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY		SAFETY	NON PARTICIPATING
				0003	0021		
STU	STE	STU					
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	117	117	-	-	
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	60	60	-	-	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-	-	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	48	48	-	-	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	291	291	-	-	
* Z0045800	PRESSURE VALVE INSERT, 8 INCH	EACH	1	-	-	1	
Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	400	400	-	-	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	881	881	-	-	
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	591	591	-	-	
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	88	88	-	-	
Z0056635	STORM SEWER (WATER MAIN REQUIREMENTS) EQUIVALENT ROUND-SIZE 30 INCH	FOOT	250	250	-	-	
Z0062456	TEMPORARY PAVEMENT	SQ YD	3,627	3,627	-	-	
Z0064560	SEGMENTAL BLOCK RETAINING WALL	SQ FT	3,888	-	3,888	-	
Δ Z0076600	TRAINEES	HOUR	500	500	-	-	
Δ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500	500	-	-	
* XX008840	DECORATIVE CROSSWALK	SQ FT	318	-	318	-	
Z0038127	THREE-SIDED PRECAST CONCRETE STRUCTURES 18'X 8'	FOOT	100	100	-	-	
* XX005476	DUCTILE IRON WATER MAIN 12" RESTRAINED JOINT TYPE	FOOT	120	-	-	120	
* XX005480	DUCTILE IRON WATER MAIN 16" RESTRAINED JOINT TYPE	FOOT	2,210	-	-	2,210	
* XX008841	WATER MAIN 8" (DIRECTIONAL BORE)	FOOT	60	-	-	60	
XX008842	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	105	105	-	-	
XX008843	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	504	504	-	-	
XX008844	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	15	15	-	-	

\* INDICATES SPECIALTY ITEM  
Δ 0042

EARTHWORK											
LOCATION	UNDERCUT	UNSUITABLE EXCAVATION (TOPSOIL)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	CHANNEL EXCAVATION	EARTH EXCAVATION	UTILITY EXCAVATION	EXCESS STRUCTURE EXCAVATION	TOTAL SUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
MAPLE AVE	6,617	1,990	8,758	-	15,739	4,162	-	19,901	16,917	2,042	14,875
TAMARAC	139	26	165	-	484	41	-	525	446	4	442
CARPENTER CREEK	-	-	-	780	-	-	-	-	-	60	(60)
<b>TOTAL</b>	<b>6,756</b>	<b>2,016</b>	<b>8,923</b>	<b>780</b>	<b>16,223</b>	<b>4,203</b>	<b>-</b>	<b>20,426</b>	<b>17,363</b>	<b>2,106</b>	<b>15,257</b>

2012 BY BAXTER & WOODMAN, INC. 11/15/11  
 LICENSE NO. 64-00018 - EXPIRES 4/30/2013  
 3/10/2013 2:28:18 PM \\npr\pub\woodman\cadd\110994-SOT1Y.shp



DESIGNED -	DJS	REVISED -	PER IDOT 10/19/12
DRAWN -	UKB	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	06/20/12	FILE -	110994-SOT1Y.shp

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
AND EARTH EXCAVATION**

F.A.U. RT#	SECTION	COUNTY	TOTAL SHEET
4006	95-00049-00-PV	KANE	138   10
CONTRACT NO. 63745			
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-8003 (095)			

SCALE: STA. TO STA.