

SUMMARY OF QUANTITIES

SPECIAL PROVISION SPECIALTY ITEM	CODE NO	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%	
					CITY = 25%	
					TRAFFIC SIGNAL 0021	SHARED-USE PATH 0028
	20109110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	52		52
A	20101200	TREE ROOT PRUNING	EACH	2		2
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,267		2,267
	21101815	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,040		1,040
	21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	50		50
	25000210	SEEDING, CLASS 2A	ACRE	0.25		0.25
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	19		19
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	19		19
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	19		19
A	25100930	EROSION CONTROL BLANKET	SQ YD	1,040		1,040
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2,267		2,267
A	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50		50
	40800100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	668		668
	40803080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	282		282
	40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	169		169
	42001300	PROTECTIVE COAT	SQ YD	1,040		1,040
A	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	21		21
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8,485		8,485
	42400800	DETECTABLE WARNINGS	SQ FT	528		528
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	122		122
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	457		457
	44000600	SIDEWALK REMOVAL	SQ FT	14,696		14,696
K	58400100	FIRE HYDRANTS TO BE MOVED	EACH	1		1
	60255500	MANHOLES TO BE ADJUSTED	EACH	4		4
A	60266600	VALVE BOXES TO BE ADJUSTED	EACH	1		1
	60803800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-8.12	FOOT	171		171
	60809200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-8.12	FOOT	286		286
	67100100	MOBILIZATION	L SUM	1		1
A	70102820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
A	70102835	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1

A SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

SPECIAL PROVISION SPECIALTY ITEM	CODE NO	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%	
					CITY = 25%	
					TRAFFIC SIGNAL 0021	SHARED-USE PATH 0028
A	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,544		1,544
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,110		2,110
*	78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	122		122
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	513		513
	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	94	94	
	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	193	193	
	81400100	HANDHOLE	EACH	1	1	
A	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	8		8
	84200804	REMOVAL OF POLE FOUNDATION	EACH	2		2
A	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	925	925	
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	951	951	
	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	76	76	
	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4	4	
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16	
	87900200	DRILL EXISTING HANDHOLE	EACH	9	9	
	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8	8	
	88800100	DETECTOR LOOP, TYPE I	FOOT	105	105	
	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8	
	89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	
	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	266	266	
A	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
*	B2000216	TREE, ACER GINNALA (AMUR MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3		3
A	M6028050	SANITARY MANHOLES TO BE ADJUSTED	EACH	4		4
A	M8380110	LIGHT POLE FOUNDATION, SPECIAL	FOOT	5		5
A	Z0069700	STABILIZED DRIVEWAYS 10"	SQ YD	71		71

Plotted: January 18, 2013 @ 1:54 PM By: Kris Pung - Top: 03 SQ 2234  
 Copyright © 2013 Engineering Enterprises, Inc.  
 Engineering Enterprises, Inc.  
 CONSULTING ENGINEERS  
 52 Wheeler Road  
 Sugar Grove, Illinois 60054  
 630.486.6700 / www.eesweb.com

USER NAME *	DESIGNED - SWM	REVISED - TVW/JPS 10/11/12
PLDT SCALE *	DRAWN - CLN	REVISED - TVW/JPS 11/30/12
PLDT DATE *	CHECKED - JRL	REVISED -
	DATE - 07/20/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	11-00032-00-BT		26	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT M-6063(641)			CONTRACT NO. 63760	

Path: \\S:\PERC\A\W\006\DWG\FINAL\_ENG\W\006-01