

[illegible]

3	SCHEDULE OF EROSION CONTROL ITEMS							
STREET	STATION		(28000400) PERIMETER EROSION BARRIER	(28000305) TEMPORARY DITCH CHECKS	(28000500) INLET AND PIPE PROTECTION	(28000510) INLET FILTERS	(28000250) TEMPORARY EROSION CONTROL SEEDING	(25100630) EROSION CONTROL BLANKET
	FROM	TO	(FOOT)	(FOOT)	(EACH)	(EACH)	(POUND)	(SQ YD)
Washington Street	200+00	5+00	563			19	21	990
	5+00	15+00	1,402	42	1	24	52	2,486
	15+00	24+00	827			16	41	1,949
	24+00	33+00	497			19	46	2,209
	33+00	43+50	266			28	74	3,557
	43+50	53+00	839		1	21	40	1,928
	53+00	63+00		42	1	3	62	2,961
PROJECT TOTAL			4,394	84	3	130	336	16,080

I	SCHEDULE OF TREE REMOVAL			
STREET	STATION		(20100110) 6 TO 15 UNITS DIAMETER	(20100210) OVER 15 UNITS DIAMETER
	FROM	TO	(UNITS)	(UNITS)
Washington Street	200+00	4+50		
	4+50	9+50		
	9+50	15+00	6	
	15+00	20+00	93	35
	20+00	25+00	26	17
	25+00	29+50	199	91
	29+50	34+50	47	
	34+50	39+50		41
	39+50	45+00	44	18
	45+00	50+50		36
	50+50	55+00		
	55+00	60+00	61	
Cedar Lake Road	60+00	63+34		
	16+70	18+50		
	18+50	22+40		
TOTAL			476	238
10% CONTINGENCY			48	24
PROJECT TOTAL			524	262

5	SCHEDULE OF AGGREGATE BASE COURSE, TYPE A (35100110)						
STREET	STATION		SIDEWALK LENGTH (3.61 SF AREA*)	PRIVATE ENTRANCE AREA (6' THICK)	COMMERCIAL ENTRANCE AREA (8' THICK)	MEDIAN AREA (12-1/2" THICK)	VOLUME
	FROM	TO	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)	(CU YD)
Washington Street	200+00	4+50	945		665	30	285
	4+50	9+50	931	48	20		137
	9+50	15+00	906	19	20		129
	15+00	20+00	941	131			148
	20+00	25+00	811	35	105		138
	25+00	29+50	716	143			120
	29+50	34+50	847	151	101		161
	34+50	39+50	868	517			203
	39+50	45+00	916	311			175
	45+00	50+50	565	268			121
	50+50	55+00		52	109		33
	55+00	60+00					
Cedar Lake Road	60+00	63+34					
	16+70	18+50	177		29		31
	18+50	22+40	366		428		144
PROJECT TOTAL							1,825

* AREA IS BASED UPON CROSS SECTION MEASUREMENT.