

DATE	BY	SURVEYED	NOTED	TEMP	AREAS CHECKED
FINAL					
SURVEY					
NOTE BOOK					
NO.					

33 SCHEDULE OF REMOVE SIGN PANEL ASSEMBLY			
STREET	STATION		TYPE A (72400100)
	FROM	TO	(EACH)
Washington Street	200+00	5+00	
	5+00	15+00	
	15+00	24+00	
	24+00	33+00	
	33+00	43+50	2
	43+50	53+00	
	53+00	63+00	
PROJECT TOTAL			2

34 SCHEDULE OF RAISED REFLECTIVE PAVEMENT MARKERS (78100100)			
STREET	STATION		TOTAL
	FROM	TO	(EACH)
Washington Street	200+00	5+00	67
	5+00	15+00	
	15+00	24+00	
	24+00	33+00	
	33+00	43+50	
	43+50	53+00	
	53+00	63+00	
PROJECT TOTAL			67

35 SCHEDULE OF TREES						
STREET	STATION		(A2000616) ACER PLATANOIDES (NORWAY MAPLE), 2" CALIPER, BALLED AND BURLAPPED	(A2002916) CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	(A2005016) GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	(A2006716) QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED
	FROM	TO	(EACH)	(EACH)	(EACH)	(EACH)
Washington Street	200+00	5+00				
	5+00	15+00				
	15+00	24+00			1	
	24+00	33+00				
	33+00	43+50	2	1	2	3
	43+50	53+00				
	53+00	63+00				
PROJECT TOTAL			2	1	3	5

36 SCHEDULE OF TEMPORARY ACCESS				
STREET	STATION		(X4021000) (PRIVATE ENTRANCE)	(X4022000) (COMMERCIAL ENTRANCE)
	FROM	TO	(EACH)	(EACH)
Washington Street	200+00	4+50		14
	4+50	9+50	4	2
	9+50	15+00	1	1
	15+00	20+00	4	
	20+00	25+00	2	2
	25+00	29+50	4	
	29+50	34+50	4	1
	34+50	39+50	13	
	39+50	45+00	10	
	45+00	50+50	9	
	50+50	55+00	2	2
	55+00	60+00		
	60+00	63+34		
	16+70	18+50		1
	18+50	22+40		3
PROJECT TOTAL			53	26

STREET	STATION		(X4023000) (ROAD)	
	FROM	TO	(EACH)	
Cedar Lake Road	16+70	18+50		1
	18+50	22+40		1
PROJECT TOTAL				25

37 SCHEDULE OF MEDIAN ITEMS			
STREET	STATION		(60618300) CONCRETE MEDIAN SURFACE, 4 INCH
	FROM	TO	(SQ FT)
Washington Street	200+00	4+50	270
	4+50	9+50	
	9+50	15+00	
	15+00	20+00	
	20+00	25+00	
	25+00	29+50	
	29+50	34+50	
	34+50	39+50	
	39+50	45+00	
	45+00	50+50	
	50+50	55+00	
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	
	18+50	22+40	
PROJECT TOTAL			270

38 SCHEDULE OF PIPE UNDERDRAINS 4" (MODIFIED) (X6013600)			
STREET	STATION		LENGTH
	FROM	TO	(FOOT)
Washington Street	200+00	4+50	1,156
	4+50	9+50	1,001
	9+50	15+00	1,148
	15+00	20+00	1,000
	20+00	25+00	1,000
	25+00	29+50	900
	29+50	34+50	1,048
	34+50	39+50	1,434
	39+50	45+00	1,100
	45+00	50+50	1,100
	50+50	55+00	
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	
	18+50	22+40	364
PROJECT TOTAL			11,251

39 SCHEDULE OF TREE PROTECTION AND PRESERVATION (XX006698)			
STREET	STATION		TOTAL
	FROM	TO	(EACH)
Washington Street	200+00	5+00	3
	5+00	15+00	4
	15+00	24+00	21
	24+00	33+00	12
	33+00	43+50	35
	43+50	53+00	15
	53+00	63+00	
PROJECT TOTAL			90

40 SCHEDULE OF DRY RUBBLE STONE OR BROKEN CONCRETE TREE WELLS (Z0019400)			
STREET	STATION		VOLUME
	FROM	TO	(CU YD)
Washington Street	200+00	4+50	
	4+50	9+50	
	9+50	15+00	
	15+00	20+00	
	20+00	25+00	
	25+00	29+50	1
	29+50	34+50	
	34+50	39+50	
	39+50	45+00	
	45+00	50+50	
	50+50	55+00	
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	
	18+50	22+40	
PROJECT TOTAL			1

DATE	BY	SURVEYED	NOTED	TEMP	AREAS CHECKED
ORIGINAL					
SURVEY					
NOTE BOOK					
NO.					