



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 24, 2013

SUBJECT: FAU 1260 (Elm Street)
Project M-4003(030)
Section 12-00097-00-PV (River Grove)
Cook County
Contract No. 63771
Item 128
April 26, 2013 Letting
Addendum (B)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Revised pages 6 & 7 of the Schedule of Prices**
- 2. Revised page 2 of the Index of Special Provisions.**
- 3. Revised page 20 of the Special Provisions.**
- 4. Revised sheets 4 & 5 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

FAU 1260
 12-00097-00-PV (RIVER GROVE)
 COOK

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63771

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 04/23/13
 RUN TIME - 183121

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
56400820	FIRE HYD W/AUX V & VB	EACH	1.000 X			=	
56500600	DOM WAT SER BOX ADJ	EACH	45.000 X			=	
56500800	DOM WAT SER BOX	EACH	10.000 X			=	
60200105	CB TA 4 DIA T1F OL	EACH	15.000 X			=	
60221100	MAN TA 5 DIA T1F CL	EACH	13.000 X			=	
60234200	INLETS TA T1F OL	EACH	8.000 X			=	
60250200	CB ADJUST	EACH	2.000 X			=	
60252800	CB RECONST	EACH	1.000 X			=	
60255500	MAN ADJUST	EACH	2.000 X			=	
60257900	MAN RECONST	EACH	22.000 X			=	
60265700	VV ADJUST	EACH	8.000 X			=	
60266100	VV RECONST	EACH	5.000 X			=	
60406000	FR & LIDS T1 OL	EACH	1.000 X			=	
60406100	FR & LIDS T1 CL	EACH	40.000 X			=	
66900200	NON SPL WASTE DISPOSL *	CU YD	2,270.000 X			=	

* Revised 4/24/13

FAU 1260
 12-00097-00-PV (RIVER GROVE)
 COOK

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63771

ECMS002 DTGECM03 ECMR003 PAGE 7
 RUN DATE - 04/23/13
 RUN TIME - 183121

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
66900400	SPL WAST GRD WAT DISP	GALLON	3,050.000 X				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000 X				
66900530	SOIL DISPOSAL ANALY *	EACH	3.000 X				
66901000	BACKFILL PLUGS	CU YD	30.000 X				
67100100	MOBILIZATION	L SUM	1.000 X				
70106800	CHANGEABLE MESSAGE SN	CAL MO	12.000 X				
70300100	SHORT TERM PAVT MKING	FOOT	400.000 X				
70301000	WORK ZONE PAVT MK REM	SQ FT	800.000 X				
72000100	SIGN PANEL T1	SQ FT	275.000 X				
72900100	METAL POST TY A	FOOT	750.000 X				
78000400	THPL PVT MK LINE 6	FOOT	250.000 X				
78000650	THPL PVT MK LINE 24	FOOT	205.000 X				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	40.000 X				
78008210	POLYUREA PM T1 LN 4	FOOT	5,000.000 X				
78008230	POLYUREA PM T1 LN 6	FOOT	850.000 X				

* Revised 4/24/13

INDEX FOR SPECIAL PROVISIONS

ITEM	PAGE
STRUCTURES TO BE RECONSTRUCTED	19
FRAMES AND LIDS, TYPE 1.....	20
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES – ELM STREET.....	20
MULCH.....	21
TEMPORARY DRAINAGE CONNECTION	21
PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	22
PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	22
STORM SEWER CONNECTION.....	22
STORM SEWER REPAIR	23
GROUND STABILIZATION GEOSYNTHETIC.....	23
RAILROAD RIGHT-OF-WAY ENTRY PERMIT.....	25
SANITARY SEWER CONNECTION.....	26
MAILBOX REMOVAL AND REPLACEMENT.....	26
DEWATERING	26
EARTH EXCAVATION (SPECIAL).....	27
TRENCH BACKFILL, SPECIAL.....	27
TOPSOIL FURNISH AND PLACE, 4" (SPECIAL).....	28
EXPLORATION TRENCH (SPECIAL)	28
TEMPORARY ACCESS (PRIVATE ENTRANCE).....	29
DUCTILE IRON STORM SEWER, 12 INCH.....	29
WATER SERVICE LINE RELOCATED.....	29
CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID, SPECIAL.....	30
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL).....	31
TRAFFIC CONTROL AND PROTECTION (SPECIAL).....	31
TRAFFIC CONTROL AND PROTECTION (ARTERIALS).....	33
REMOVE AND RE-ERECT EXISTING SIGN	33
PAVING BRICK PAVEMENT FOR LIGHT TRAFFIC.....	34
DRAINAGE STRUCTURES TO BE REMOVED	34
DUST CONTROL WATERING	35
TEMPORARY INFORMATION SIGNING.....	35
SAW CUTTING.....	36
TEMPORARY PAVEMENT	36

DISTRICT ONE SPECIAL PROVISIONS

COARSE AGGREGATE FOR BACKFILL, TRENCH BACKFILL, AND BEDDING (D-1)	37
FINE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1).....	37
RECLAIMED ASPHALT PAVEMENT AND SHINGLES (D-1).....	37

Revised 4/24/13

All trench backfill used to fill around the new structure will be included in the cost of this item.

Basis of Payment: This item shall be paid for at the Contract unit price per Each for CATCH BASINS TO BE RECONSTRUCTED, MANHOLES TO BE RECONSTRUCTED, or VALVE VAULTS TO BE RECONSTRUCTED.

FRAMES AND LIDS, TYPE I

All sewer closed lids shall be provided according to Section 604 of the "Standard Specifications" and shall be self-sealing with recessed pick holes. All frames with closed lids to be furnished as part of this contract for construction, adjustment, or reconstruction of any manhole or valve vault shall have cast into the lid one of the following words:

<u>Structure Type</u>	<u>Neenah Foundry* Frame and Lid</u>	<u>Self Sealing</u>	<u>Word Cast Into Lid</u>
Sanitary Manhole	R-1713-B	YES	SANITARY
Combination Manhole	R-1713-B	YES	SANITARY
Storm Manhole	R-1713-B	NO	STORM
Valve Vault	R-1713-B	YES	WATER
Catch Basin	R-2504-D	NO	-----
Inlet	R-2504-D	NO	-----

* Note: Or engineer approved equal.

Basis of Payment: The frame and lid shall be included in the unit price of any new structure placed as part of the project. In the case of an existing structure that is to be adjusted or reconstructed the frame and lid shall be paid for at the Contract unit price per Each for FRAMES AND LIDS, TYPE 1, CLOSED LID or FRAMES AND LIDS, TYPE 1, OPEN LID.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES – ELM STREET

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.