

SUMMARY OF QUANTITIES

CODE NO.		ITEM	UNIT	TOTAL QUANTITY	0028
20100110	*	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	166	166
20100210	*	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	17	17
20101000		TEMPORARY FENCE	FOOT	330	330
20101200		TREE ROOT PRUNING	EACH	10	10
20200100	*	EARTH EXCAVATION	CU YD	22,457	22,457
20201200		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,000	1,000
20400800	*	FURNISHED EXCAVATION	CU YD	1,624	1,624
20800150	*	TRENCH BACKFILL	CU YD	110	110
21001000		GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,100	1,100
21101615	^ *	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	18,000	18,000
21400100		GRADING AND SHAPING DITCHES	FOOT	1,650	1,650
25000400	^	NITROGEN FERTILIZER NUTRIENT	POUND	335	335
25000600	^	POTASSIUM FERTILIZER NUTRIENT	POUND	335	335
25100630	*	EROSION CONTROL BLANKET	SQ YD	18,000	18,000
28000250	^	TEMPORARY EROSION CONTROL SEEDING	POUND	550	550
28000305	*	TEMPORARY DITCH CHECKS	FOOT	150	150
28000400	*	PERIMETER EROSION BARRIER	FOOT	2,370	2,370
28000510		INLET FILTERS	EACH	8	8
28100105		STONE RIPRAP, CLASS A3	SQ YD	10	10
28200200		FILTER FABRIC	SQ YD	10	10
30300112		AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	165	165
35100500		AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	1,100	1,100
35101700		AGGREGATE BASE COURSE, TYPE B 5"	SQ YD	455	455
40200800		AGGREGATE SURFACE COURSE, TYPE B	TON	65	65
40201000	*	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200
40600100		BITUMINOUS MATERIALS (PRIME COAT)	GALLON	300	300
40603080		HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	95	95
40603335		HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	235	235
44000100		PAVEMENT REMOVAL	SQ YD	265	265
48101200	*	AGGREGATE SHOULDERS, TYPE B	TON	65	65
50200100		STRUCTURE EXCAVATION	CU YD	7,010	7,010

* DENOTES SPECIAL PROVISION
^ DENOTES SPECIALTY ITEM
^^ DENOTES CONSTRUCTION TYPE CODE 0042

CODE NO.		ITEM	UNIT	TOTAL QUANTITY	0028
50300225		CONCRETE STRUCTURES	CU YD	699	699
50300254		RUBBED FINISH	SQ FT	4,707	4,707
50800205		REINFORCEMENT BARS, EPOXY COATED	POUND	95,770	95,770
50800515		BAR SPLICERS	EACH	116	116
51500100		NAME PLATES	EACH	1	1
54213660		PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
54213663		PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1
54213675		PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1
54213870		STEEL END SECTIONS 15"	EACH	2	2
5422A015		PIPE CULVERTS, CLASS A, TYPE 2 15" (TEMPORARY)	FOOT	78	78
54244405		FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	5	5
550A0050		STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	90	90
550A0070		STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	24	24
550A0360		STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	171	171
550A0380		STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	24	24
550A0410		STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	93	93
550A0430		STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	389	389
58000100		MEMBRANE WATERPROOFING	SQ FT	300	300
59100100		GEOCOMPOSITE WALL DRAIN	SQ YD	573	573
60207605		CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1
60218400		MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60235300		INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1
66900200	^	NON-SPECIAL WASTE DISPOSAL	CU YD	200	200
66900530	^ *	SOIL DISPOSAL ANALYSIS	EACH	4	4
67100100		MOBILIZATION	L SUM	1	1
70106800		CHANGEABLE MESSAGE SIGN	CAL MO	8	8
70301000		WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	816	816
70400100		TEMPORARY CONCRETE BARRIER	FOOT	250	250
70400200		RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	250	250
70600240		IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
70600340		IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
78000200	^	THERMOPLASTIC PAVEMENT MARKINGS - LINE 4"	FOOT	200	200