

SUMMARY OF QUANTITIES				0005 ROADWAY 50% STP 50% LA
CODE NO	PAY ITEM	UNIT	QUANTITY	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	98	98
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	424	424
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8	8.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	8.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8	8.0
25200110	SODDING, SALT TOLERANT	SQ YD	424	424
25200200	SUPPLEMENTAL WATERING	UNIT	5	5.0
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	50	50
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,079	1,079
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,606	11,606
40600300	AGGREGATE (PRIME COAT)	TON	232	232
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,192	3,192
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	415	415
40600990	TEMPORARY RAMP	SQ YD	1,351	1,351
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,875	4,875
42001300	PROTECTIVE COAT	SQ YD	1,062	1,062
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	61	61
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6,405	6,405
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	256	256
42400800	DETECTABLE WARNINGS	SQ FT	710	710
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	58,030	58,030
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	78	78
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,271	1,271
44000600	SIDEWALK REMOVAL	SQ FT	7,061	7,061
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	125	125
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	125	125
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	125	125
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	125	125
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
60404305	FRAMES AND GRATES, TYPE 3V	EACH	2	2
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	1	1
60500060	REMOVING INLETS	EACH	2	2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	596	596
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	675	675
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,365	1,365
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	874	874
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,606	6,606
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,632	3,632
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,029	1,029
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,893	1,893
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	486	486
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	842	842
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	874	874
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,606	6,606

SUMMARY OF QUANTITIES				0005 ROADWAY 50% STP 50% LA
CODE NO	PAY ITEM	UNIT	QUANTITY	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,632	3,632
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,029	1,029
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,893	1,893
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	486	486
88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,047	2,047
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	2	2
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	180	180
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	201	201.0
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	17	17
Z0013796	CONSTRUCTION LAYOUT	L SUM	1	1
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	10	10
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2	2
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	89	89
Z0076600	TRAINEES	HOUR	500	500
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500	500

△ CONSTRUCTION TYPE CODE 0042

• SPECIALTY ITEM

FILE NAME =	USER NAME = JUSER	DESIGNED - CEC	REVISED -
D:\CN\2\2074\Road\Sheet\0-103-50m04.dwg		DRAWN - CEC	REVISED -
	PLOT SCALE = 6.34932 FT / IN.	CHECKED - DWB	REVISED -
	PLOT DATE = 2/11/2013	DATE - 02/11/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RICKERT DRIVE RESURFACING
SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2540	12-00155-00-RS		21	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 63789	