



- NOTES:
- 1) CLASS D PATCHES, 12" AS DIRECTED BY ENGINEER
  - 2) THE ADJUSTMENT OF THE DRAINAGE STRUCTURES IN THE CURB AND GUTTER LINE SHALL BE PAID FOR AS DRAINAGE STRUCTURES TO BE ADJUSTED.
  - 3) REMOVAL AND DISPOSAL OF THE MATERIAL UNDER THE PROPOSED CURB AND GUTTER LOCATION IN ORDER TO INSTALL THE PROPOSED SUB-BASE GRANULAR MATERIAL, TY B 4" UNDER THE PROPOSED CURB AND GUTTER SHALL BE CONSIDERED INCLUDED IN THE COST OF COMB CURB AND GUTTER REMOVAL. EARTH EXCAVATION AND BACKFILL IN ORDER TO INSTALL THE PROPOSED CURB AND GUTTER SHALL BE INCLUDED IN THE COST OF THE PROPOSED CURB AND GUTTER.
  - 4) IN LOCATIONS WHERE DRAINAGE STRUCTURES ARE BEING ADJUSTED AND THERE IS B-6.12 CURB AND GUTTER, THERE SHALL BE A 5" TRANSITION ON EACH SIDE OF THE DRAINAGE STRUCTURE FOR THE FACE OF CURB TO BE TRANSITIONED FROM 12" TO 18" OFF EDGE OF PAVEMENT.

LEGEND

[A]	DRAINAGE STRUCTURES TO BE ADJUSTED
[RISP]	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL
[F&G 3V]	NEW FRAME & GRATE, TYPE 3V
[F&L I CL]	NEW FRAME & LID, TYPE I, CLOSED LID
[VBA]	VALVE BOX TO BE ADJUSTED
[Hatched Box]	SOODING, SALT TOLERANT TOPSOIL FURNISH AND PLACE, 4"

FILE NAME = g:\ch12\20774\road\sheet4\120874-R04D-4.dwg	USER NAME = _USER_	DESIGNED - CEC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>RICKERT DRIVE RESURFACING ROADWAY PLAN</b>			F.A.U. RTE. 2540	SECTION 12-00165-00-RS	COUNTY	TOTAL SHEETS 21	SHEET NO. 8
PLT SCALE = #SCALE#	CHECKED - DAB	REVISED -	REVISED -		SCALE: 1"=50'	SHEET 4 OF 4 SHEETS	STA. 169+00 TO STA. 188+62.47	DUPAGE	CONTRACT NO. 63789		ILLINOIS FED. AID PROJECT	
PLT DATE = 2/12/2013	DATE - 02/11/2013	REVISED -	REVISED -									