

SUMMARY OF QUANTITIES

| CODE NO. | PAY ITEM | UNITS | QTY. | | CODE NO. | PAY ITEM | UNITS | QTY. |
|------------|---|-------|--|--|--------------|---|-------|--|
| | | | CONSTRUCTION TYPE CODE 0005 | | | | | CONSTRUCTION TYPE CODE 0005 |
| ~ X6030310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 5 | | 60206905 | CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID | EACH | 1 |
| 31101200 | SUB-BASE GRANULAR MATERIAL, TYPE B 4" | SQ YD | 37 | | 60234200 | INLETS, TYPE A, TYPE 1 FRAME, OPEN LID | EACH | 1 |
| 35102000 | AGGREGATE BASE COURSE, TYPE B 8" | SQ YD | 58 | | 60250400 | CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID | EACH | 1 |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 23 | | 60266300 | VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID | EACH | 1 |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GAL | 2919 | | 60266600 | VALVE BOXES TO BE ADJUSTED | EACH | 2 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 1 | | 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 2 |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 109 | | 60500050 | REMOVING CATCH BASINS | EACH | 1 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT | SQ YD | 44 | | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 2367 |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 600 | | 67100100 | MOBILIZATION | L SUM | 1 |
| ~ 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 37 | | 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 |
| 44000160 | HOT-MIX ASPHALT SURFACE REMOVAL, 2-3/4" | SQ YD | 3892 | | * 78000100 | THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS | SQ FT | 61.20 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 629 | | * 78000200 | THERMOPLASTIC PAVEMENT MARKING- LINE 4" | FOOT | 2384 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 2367 | | * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 109 |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 389 | | * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 48 |
| 44300100 | AREA REFLECTIVE CRACK CONTROL TREATMENT | SQ YD | 3892 | | ~ * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 224 |
| 60200105 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME OPEN LID | EACH | 4 | | | | | |

* DENOTES SPECIALTY ITEM

~ DENOTES SPECIAL PROVISION ITEM

| | | | | | | | | | |
|--|-----------------|----------------|---|------------------------------|--------------------|--------------------------|---------------------|-----------------|------------------|
| CENTRAL AVENUE STA 10+00 TO STA 22+12 | DRAWN BY: JMH | REVISED: _____ | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | FAU RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | CHECKED BY: SAL | REVISED: _____ | | | FAP RT 366 | 12-00036-00-RS | COOK | 12 | 3 |
| | DATE: 12.04.12 | REVISED: _____ | | | CONTRACT No. 63790 | | | | |
| | REVISED: _____ | REVISED: _____ | | | SCALE: N.T.S. | SHEET No. 3 OF 12 SHEETS | FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |