



- NOTES:
- HOT-MIX ASPHALT SURFACE REMOVAL DEPTH WITHIN NORTH AVE, R.O.W. SHALL BE ADJUSTED TO 2 1/4". GRINDING OPERATIONS MAY INCLUDE PORTION OF EXISTING CONCRETE BASE. PROPOSED PAVEMENT SECTION SHALL BE HMA LEVELING BINDER, 3/4" AND HMA SURFACE COURSE, 1 1/2".
 - CONTRACTOR TO DETERMINE CUTS AND SIZES OF PIPE FOR PROPOSED REPLACEMENT STRUCTURES NEAR THE INTERSECTION OF ROBERTA AVENUE AND THE NORTH AVENUE FRONTAGE ROAD.

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY PLANS ROBERTA AVENUE			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
NONDRIT-LAKE\948032DC122\01v:1\p1h3_rpb	ca_dec122.sht	DRAWN -	REVISED -					2539	12-00080-00-RS	COOK	18	11
	PLCT SCALE = 20'	CHECKED -	REVISED					CONTRACT NO. 63791				
	PLCT DATE = 2/26/2013	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			