

SUMMARY OF QUANTITIES

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%	
					VILLAGE = 25%	
					ROADWAY	
					0005	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	185	185	
	25200110	SODDING, SALT TOLERANT	SQ YD	185	185	
	25200200	SUPPLEMENTAL WATERING	UNIT	9	9	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,660	1,660	
	40600300	AGGREGATE (PRIME COAT)	TON	33	33	
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3	
A	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	581	581	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	151	151	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	930	930	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,743	1,743	
	42400800	DETECTABLE WARNINGS	SQ FT	136	136	
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	8,290	8,290	
	44000600	SIDEWALK REMOVAL	SQ FT	1,779	1,779	
	44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10	
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	235	235	
	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	124	124	
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	250	250	
	50260100	INLETS TO BE ADJUSTED	EACH	2	2	
A	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	7	7	
A	60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	525	525	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	175	175	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	145	145	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,494	4,494	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	459	459	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	507	507	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	114	114	
A *	88600600	DETECTOR LOOP REPLACEMENT	FOOT	165	165	
A	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	11	11	
A	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6	
A *	X8140115	HANDHOLE TO BE ADJUSTED	EACH	1	1	
A	XX006847	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	112	112	
A	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	355	355	

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Plotted: February 15, 2013 11:15 AM By: Kris Pung - Tab: 03 Sum of Quan 22a34

Engineering Enterprises, Inc.  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeinc.com

USER NAME *	DESIGNED -	REVISED -
PLOT SCALE *	DRAWN -	REVISED -
PLOT DATE *	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2508	12-00048-00-R5	KANE	16	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT - STP			CONTRACT NO. 63793	

PART: 12505SPRUCY.MOT177.DWG.V016.FINAL ENG.MOT17-006