



END IMPROVEMENTS  
STA 55+70  
DOUGLAS RD.

HOT-MIX ASPHALT DRIVEWAY  
REMOVAL AND REPLACEMENT,  
10 SQ. YD.

COMBINATION CURB & GUTTER  
REMOVAL AND REPLACEMENT,  
44 LF

- HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4", 1940 SQ YD
- BITUMINOUS MATERIALS (PRIME COAT), 390 GALLONS
- AGGREGATE (PRIME COAT), 8 TONS
- POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 1.25", 136 TONS
- HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 2.0", 218 TONS

NOTE: ALL MANHOLES TO BE  
ADJUSTED SHALL BE PAID  
FOR AS FRAME AND LIDS  
TO BE ADJUSTED (SPECIAL)

Printed: January 28, 2013 @ 2:34 PM By: Larry Nelson - Tab: 08 Plan 22x34

Engineering Enterprises, Inc.  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60654  
630.468.6700 / www.eeiweb.com

|              |            |           |
|--------------|------------|-----------|
| USER NAME =  | DESIGNED - | REVISED - |
| PLOT SCALE = | DRAWN -    | REVISED - |
| PLOT DATE =  | CHECKED -  | REVISED - |
|              | DATE -     | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GENERAL PLAN**

SCALE: 1"=30' SHEET NO. 2 OF 2 SHEETS STA. 50+50 TO STA. 55+70

| F.A.U. RTE.   | SECTION        | COUNTY | TOTAL SHEETS       | SHEET NO. |
|---|----------------|--------|--------------------|-----------|
| 2508  | 12-00048-00-RS | KANE   | 16                 | 8         |
| FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT - STP |                |        | CONTRACT NO. 63793 |           |