



**NOTES:**

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

PRINTED DATE: 2/1/2013  
 FILE NAME: K:\Projects\Baltimore\Baltimore\Road Culvert\Schmidt, Rd over Lily Cade Ph. 2\CAD\Drawings\Sheet\25 DISTRICT L TC-22.dgn



USER NAME = #USER#	DESIGNED - JC	REVISED -
	DRAWN - DN	REVISED -
PLOT SCALE = 1/8000" = 1/ IN.	CHECKED - MR	REVISED -
PLOT DATE = 2/1/2013	DATE - 2/1/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD INFORMATION SIGN- TC-22

F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
2571	09-00053-00-BR	WILL	25	25
CONTRACT NO.: 63797			ILLINOIS FEDERAL AID PROJECT	