

DATE	
BY	
PLAN	
NO.	
DATE	
BY	
PROFILE	
NO.	
DATE	
BY	

DATE	
BY	
PROFILE	
NO.	
DATE	
BY	

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0021
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,230	1,230
~	25000100	SEEDING, CLASS 1	ACRE	0.25	0.25
	35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	3,035	3,035
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	14	14
~	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	26,845	26,845
~	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	135	135
~	42400800	DETECTABLE WARNINGS	SQ FT	188	188
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	28	28
~	44000600	SIDEWALK REMOVAL	SQ FT	20,125	20,125
~	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	4	4
	60600605	CONCRETE CURB, TYPE B	FOOT	20	20
	67100100	MOBILIZATION	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
	* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	310	310
	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70
~	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	135	135
~	X2520650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	90	90
~	XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	14	14
~	Z0004562	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	25	25

GENERAL NOTES:

- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF MERRIONETTE PARK.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE. USE ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- ALL PAVEMENT, CURB, SIDEWALK AND DRIVEWAY REMOVALS SHALL BE MADE BY MEANS OF STRAIGHT SAW CUT JOINT. THE COST FOR SAW CUTTING SHALL BE INCLUDED IN THE COST OF THE INDIVIDUAL ITEMS BEING REMOVED
- THE CONTRACTOR MAY PROSECUTE WORK BETWEEN THE HOURS OF 7:00 A.M. AND DUSK EACH WORKDAY. NO WORK WILL BE PERMITTED ON SUNDAYS, OR ON HOLIDAYS, WITHOUT PRIOR WRITTEN PERMISSION FROM THE ENGINEER.

BENCH MARK:

MAG NAIL IN PAVEMENT IN NORTHWEST INTERSECTION OF MEADOW LAND DRIVE AND PALISADES DRIVE.
ELEVATION=519.45 (NAVD 88)

* - INDICATES SPECIALTY ITEMS
~ - INDICATES SPECIAL PROVISIONS

FILE NAME = 12260_01-QUAN-01 - IDOT P01

USER NAME =	DESIGNED -- TAG	REVISED --
	CHECKED -- PKB	REVISED --
PLOT SCALE = N/A	DRAWN -- KWM	REVISED --
PLOT DATE = 02-01-13	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK REPLACEMENT
SUMMARY OF QUANTITIES
VILLAGE OF MERRIONETTE PARK

SCALE: N/A SHEET NO. 02 OF 08 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	12-00030-00-SW	COOK	08	02
CONTRACT NO. 63799				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT SRTS-4008(181)				