

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				HBP - 80% FEDERAL, 20% LOCAL	BRIDGE 0014
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SO YD	2,666		2,666
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	116		116
△ 44000100	PAVEMENT REMOVAL	SO YD	2,858		2,858
△ 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	440		440
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	302		302
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	128		128
50102400	CONCRETE REMOVAL	CU YD	85.6		85.6
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	168		168
50300225	CONCRETE STRUCTURES	CU YD	121.3		121.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	696.5		696.5
50300260	BRIDGE DECK GROOVING	SO YD	1,926		1,926
50300300	PROTECTIVE COAT	SO YD	2,245		2,245
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	238,210		238,210
50500505	STUD SHEAR CONNECTORS	EACH	6,996		6,996
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1		1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	159,240		159,240

- (1) CONSTRUCTION TYPE CODE 0042  
 • SPECIALTY ITEMS  
 △ SPECIAL PROVISION

FILE NAME: I:\PROJECTS\08-008-000\Drawings\Notes\Sheets\03-028-00-00-001.dgn



**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5507 North Cumberland Avenue, Suite 402  
 Chicago, Illinois 60655  
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = jk.jellison	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 1/29/2013	CHECKED -	REVISED -
	DATE = 1/29/2013	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

FAU 298 (BLACK ROAD) OVER THE DUPAGE RIVER  
 SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

C.H. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
298	04-00069-18-BR	WILL	51	4
CONTRACT NO. 63803				ILLINOIS FED. AID PROJECT