

| 20100110                              |          |      |
|---------------------------------------|----------|------|
| TREE REMOVAL (6 TO 15 UNITS DIAMETER) |          |      |
| STA                                   | LOCATION | UNIT |
| 16+76                                 | RT       | 7    |
| 16+77                                 | RT       | 12   |
| 16+81                                 | RT       | 6    |
| TOTAL                                 |          | 25   |

| 48101500                       |                          |        |       |       |       |
|--------------------------------|--------------------------|--------|-------|-------|-------|
| AGGREGATE SHOULDERS, TYPE B 6" |                          |        |       |       |       |
| STA                            | LOCATION                 | LENGTH | WIDTH | SQ YD |       |
| 17+16                          | NW FRONTAGE RD (N. SIDE) | LT     | 149   | 2.75  | 147.0 |
| 17+16                          | NW FRONTAGE RD (S. SIDE) | RT     | 91    | 2.75  | 154.6 |
| TOTAL                          |                          |        |       |       | 302   |

| 63100167   |          |      |
|--|----------|------|
| TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT |          |      |
| STA  | LOCATION | EACH |
| 13+07.33   | RT       | 1    |
| 12+69.83   | LT       | 1    |
| NW FRONTAGE RD (S. SIDE)                           |          | 1    |
| NW FRONTAGE RD (N. SIDE)                           |          | 1    |
| TOTAL  |          | 4    |

| 40701956                                       |       |        |         |         |       |
|--|-------|--------|---------|---------|-------|
| HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4" |       |        |         |         |       |
| STA  | STA   | LENGTH | WIDTH 1 | WIDTH 2 | SQ YD |
| BLACK RD                                       |       |        |         |         |       |
| 12+00  | 12+86 | 86     | 48.0    | 48.0    | 458.7 |
| 12+86  | 14+05 | 119    | 48.0    | 52.8    | 666.4 |
| BRIDGE   |       |        |         |         |       |
| 17+38  | 18+72 | 134    | 56.8    | 51.2    | 804.0 |
| 18+72  | 18+81 | 9      | 3.2     | 3.2     | 3.2   |
| FRONTAGE RD (SOUTH OF BLACK RD)                |       |        |         |         |       |
| 17+37  | 17+51 | 14     | 0.0     | 7.0     | 5.4   |
| 17+51  | 17+57 | 6      | 7.0     | 18.6    | 8.5   |
| 17+57  | 17+62 | 5      | 18.6    | 28.7    | 13.1  |
| 17+62  | 17+68 | 6      | 28.7    | 59.0    | 29.2  |
| 17+68  | 17+92 | 24     | 59.0    | 60.4    | 159.2 |
| 17+92  | 17+96 | 4      | 60.4    | 36.9    | 21.6  |
| 17+96  | 18+05 | 9      | 36.9    | 18.1    | 27.5  |
| 18+05  | 18+22 | 17     | 18.1    | 4.5     | 21.3  |
| 18+22  | 18+44 | 22     | 4.5     | 0.0     | 5.5   |
| FRONTAGE RD (NORTH OF BLACK RD)                |       |        |         |         |       |
| 17+63  | 17+78 | 15     | 0.0     | 5.1     | 4.3   |
| 17+78  | 17+89 | 11     | 5.1     | 16.5    | 13.2  |
| 17+89  | 18+26 | 37     | 16.5    | 82.7    | 203.9 |
| 18+26  | 18+45 | 19     | 82.7    | 72.3    | 163.6 |
| 18+45  | 18+48 | 3      | 72.3    | 28.5    | 16.8  |
| 18+48  | 18+61 | 13     | 28.5    | 10.7    | 28.3  |
| 18+61  | 18+81 | 20     | 10.7    | 0.0     | 11.9  |
| TOTAL  |       |        |         |         | 2666  |

| 48203021                      |       |          |        |       |       |
|-------------------------------|-------|----------|--------|-------|-------|
| HOT-MIX ASPHALT SHOULDERS, 6" |       |          |        |       |       |
| STA                           | STA   | LOCATION | LENGTH | WIDTH | SQ YD |
| 12+72                         | 12+96 | RT       | 24     | 2.9   | 7.7   |
| 12+96                         | 13+07 | RT       | 11     | 5.8   | 7.1   |
| 13+07                         | 13+44 | RT       | 37     | 4.3   | 17.7  |
| 13+44                         | 14+26 | RT       | 82     | 2.8   | 25.5  |
| 12+35                         | 12+59 | LT       | 24     | 2.9   | 7.7   |
| 12+59                         | 12+70 | LT       | 11     | 5.8   | 7.1   |
| 12+70                         | 13+07 | LT       | 37     | 4.3   | 17.7  |
| 13+07                         | 14+26 | LT       | 119    | 2.8   | 37.0  |
| TOTAL                         |       |          |        |       | 128   |

| 63200310          |                          |          |      |
|-------------------|--------------------------|----------|------|
| GUARDRAIL REMOVAL |                          |          |      |
| STA               | STA                      | LOCATION | FOOT |
| 12+76             | 14+28                    | LT       | 152  |
| 13+03             | 14+28                    | RT       | 125  |
| BRIDGE            |                          |          |      |
| 17+14             | NW FRONTAGE RD (N. SIDE) | LT       | 481  |
| 17+17             | NW FRONTAGE RD (S. SIDE) | RT       | 501  |
| TOTAL             |                          |          | 1259 |

| 60605000  |       |          |      |
|---|-------|----------|------|
| COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 |       |          |      |
| STA   | STA   | LOCATION | FOOT |
| 12+00   | 14+05 | LT       | 205  |
| 12+00   | 14+05 | RT       | 205  |
| BRIDGE  |       |          |      |
| TOTAL   |       |          | 410  |

| 72000100            |       |          |        |       |       |
|---------------------|-------|----------|--------|-------|-------|
| SIGN PANEL - TYPE 1 |       |          |        |       |       |
| TYPE                | STA   | LOCATION | LENGTH | WIDTH | SQ FT |
| R1-1                | 18+21 | LT       | 3.0    | 3.0   | 9     |
| R1-1                | 18+06 | RT       | 3.0    | 3.0   | 9     |
| TOTAL               |       |          |        |       | 18    |

| 42001430                                      |       |       |        |       |       |
|---|-------|-------|--------|-------|-------|
| BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) |       |       |        |       |       |
| BRIDGE  | STA   | STA   | LENGTH | WIDTH | SQ YD |
| BRIDGE OVER DUPAGE RIVER                      | 14+05 | 14+11 | 6.0    | 52.8  | 35.2  |
| BRIDGE  |       |       |        |       |       |
| BRIDGE OVER DUPAGE RIVER                      | 17+31 | 17+37 | 6.0    | 56.8  | 37.9  |
| NW FRONTAGE RD                                |       |       |        |       |       |
| BRIDGE OVER I-55                              | 18+66 | 18+72 | 6.0    | 56.4  | 37.6  |
| BRIDGE OVER I-55                              | 18+72 | 18+81 | 9.0    | 5.0   | 5.0   |
| TOTAL   |       |       |        |       | 116   |

| 63000003   |                          |          |       |
|--|--------------------------|----------|-------|
| STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS |                          |          |       |
| STA  | STA                      | LOCATION | FOOT  |
| 13+19.83   | 13+82.33                 | LT       | 62.5  |
| 13+57.33   | 13+82.33                 | RT       | 25.0  |
| 17+60.08   | NW FRONTAGE RD (N. SIDE) | LT       | 387.5 |
| 17+53.32   | NW FRONTAGE RD (S. SIDE) | RT       | 412.5 |
| TOTAL  |                          |          | 887.5 |

| 72400100                            |       |          |      |
|-------------------------------------|-------|----------|------|
| REMOVE SIGN PANEL ASSEMBLY - TYPE A |       |          |      |
| TYPE                                | STA   | LOCATION | EACH |
| R1-1                                | 18+21 | LT       | 1    |
| R1-1                                | 18+06 | RT       | 1    |
| TOTAL                               |       |          | 2    |

| 44000500                            |       |          |      |
|-------------------------------------|-------|----------|------|
| COMBINATION CURB AND GUTTER REMOVAL |       |          |      |
| STA                                 | STA   | LOCATION | FOOT |
| 12+00                               | 14+20 | LT       | 220  |
| 12+00                               | 14+20 | RT       | 220  |
| TOTAL                               |       |          | 440  |

| 63100085                         |          |      |
|----------------------------------|----------|------|
| TRAFFIC BARRIER TERMINAL, TYPE 6 |          |      |
| STA                              | LOCATION | EACH |
| 14+26.08                         | LT       | 1    |
| 14+26.08                         | RT       | 1    |
| BRIDGE                           |          |      |
| 17+16.42                         | LT       | 1    |
| 17+16.42                         | RT       | 1    |
| TOTAL                            |          | 4    |

FILE NAME: N:\PROJ\0050108\0050108.Dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

|                           |                  |           |
|---------------------------|------------------|-----------|
| USER NAME = jkellman      | DESIGNED -       | REVISED - |
| PLOT SCALE = 2.0000' / 1" | DRAWN -          | REVISED - |
| PLOT DATE = 1/29/2013     | CHECKED -        | REVISED - |
|                           | DATE = 1/29/2013 | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAU 298 (BLACK ROAD) OVER THE DUPAGE RIVER  
SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

|                    |                        |             |                           |             |
|--------------------|------------------------|-------------|---------------------------|-------------|
| C.H. RTE. 298      | SECTION 04-00069-18-BR | COUNTY WILL | TOTAL SHEETS 51           | SHEET NO. 8 |
| CONTRACT NO. 63803 |                        |             | ILLINOIS FED. AID PROJECT |             |