

SUMMARY OF QUANTITIES				CONS TYPE CODE	
CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0028 BICYCLE/PED TRAILS	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	69	69	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	30	30	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	30	30	
20200100	EARTH EXCAVATION	CU YD	1712	1712	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1509	1509	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	200	200	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5238	5238	
25200110	SODDING, SALT TOLERANT	SQ YD	5238	5238	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65	65	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65	65	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65	65	
25200200	SUPPLEMENTAL WATERING	UNIT	79	79	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	336	336	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28000510	INLET FILTERS	EACH	27	27	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	100	100	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	944	944	
35101700	AGGREGATE BASE COURSE, TYPE B 5"	SQ YD	4729	4729	
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	1	1	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2081	2081	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	795	795	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8496	8496	
42400800	DETECTABLE WARNINGS	SQ FT	136	136	
44000100	PAVEMENT REMOVAL	SQ YD	38	38	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	150	150	
44000600	SIDEWALK REMOVAL	SQ FT	236	236	
50105220	PIPE CULVERT REMOVAL	FOOT	25	25	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	7	7	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	150	150	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	68	68	

SUMMARY OF QUANTITIES				CONS TYPE CODE	
CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0028 BICYCLE/PED TRAILS	
Δ 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3	
Δ 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	27	27	
Δ 72900100	METAL POST - TYPE A	FOOT	315	315	
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	263	263	
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	293	293	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	130	130	
* X0326806	WASHOUT BASIN	L SUM	1	1	
* X2800310	REMOVE PERIMETER EROSION BARRIER	FOOT	5848	5848	
* X5121800	PERMANENT STEEL SHEET PILING	SQ FT	3905	3905	
* Δ X6330800	GUARDRAIL POST VERTICAL ADJUSTMENT	EACH	20	20	
* Δ X7240505	RELOCATE SIGN PANEL AND POST	EACH	8	8	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	

Δ DENOTES SPECIALTY ITEM
* DENOTES SPECIAL PROVISION



77 W. Hintz Rd, Wheeling, IL 60090 (847) 279-6900

DATE: _____ DESIGNED: SW
DRAWN: MT
PLOT SCALE: _____ CHECKED: JS
PLOT DATE: _____ DATE: 1/30/13

REVISED: _____
REVISED: _____
REVISED: _____
REVISED: _____

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	10-00072-00-BT	COOK	39	3
CONTRACT NO. 63805				
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	FAP-343	