

M:\PROJECTS\11-0015\11-0015-00-RS\Schedule.dgn

SUMMARY SCHEDULE OF EARTH QUANTITIES					
LOCATION	VOLUME (CU YD)				
	20201200 UNSUITABLE	20200100 EARTH EX	EXCAVATION (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE
STA 40+18 TO 41+25	65.2	11.7	9.9	80.5	-70.6
STA 41+54 TO STA 42+40	53.2	14.4	12.2	155.1	-142.9
STA 44+45 TO STA 44+60	8.2	14.6	12.4	0.4	12.0
STA 44+87 TO STA 48+20	264.7	728.8	619.5	106.4	513.1
STA 48+54 TO STA 54+55	365.2	56.7	48.2	709.2	-661.0
POTENTIAL UNSUITABLE UNDER PAT	344.7	0.0	0.0	0.0	0.0
PROJECT TOALS	1,101.2	826.2	702.3	1,051.6	-349.3

ENGINEERING CONSULTANT

Glomba Group, Inc.
 CONSULTING ENGINEERS
 5507 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60630
 Tel: 773.776.6000 Fax: 773.776.4014
 Email: chicago@glomba.com

USER NAME = ahern
 PLOT SCALE = 50.0000' / 1" =
 PLOT DATE = 2/22/2013

DESIGNED - RJR
 DRAWN - AMH
 CHECKED - MRJ
 DATE - FEBRUARY 4, 2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**MCHENRY AVENUE
 EARTHWORK SCHEDULE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
120	11-0015-00-RS	MCHENRY	62	9
CONTRACT NO. 63806			ILLINOIS FED. AID PROJECT	